


TREE INVENTORY CHART -- TABLE 1

	Guelph Trunk Sewer 10-12-108			rk Complete	d By: Ben	Tymchysh	yn				
	ield Work: 12/19/2012		Weather:		TT - T4 4 - X					D	Conditions: G - Good, F - Fair, P - Poor, D - Dead
#	Botanical Name	Common Name	No.	DBH (cm)	Height (m)	Trunk	Condition Canopy	Vigour	Dripline Radius	Recommendation	Remarks
001	Picea glauca	Colorado Spruce	1	37	12	F	F	F		retain	canker
002	Picea glauca	Colorado Spruce	1	34	12	F	F	F		retain	canker
003	Picea glauca	Colorado Spruce	1	29	12	Р	Р	Р		retain	canker
004	Acer platanoides	Norway Maple	1	22	7	G	G	G		retain	
005	Acer platanoides	Norway Maple	1	36	12	G	G	G		retain	
006	Fraxinus sp.	Ash	1	50	14	F	F	F		retain	
007	Fraxinus sp.	Ash	1	40	14	F	F	F		retain	suckers, 30% deadw ood, trunk w ounds
008	Fraxinus sp.	Ash	1	42	15	F	F	F		retain	30% deadw ood, lean, trunk w ounds
009	Acer platanoides	Norway Maple	1	41	10	g	F	F		retain	
G-010	GroupingPicea glauca	Colorado Spruce	3	32	10	Р	Р	Р		retain	3 trees all w ith canker
011	Picea glauca	Colorado Spruce	1	40	12	Р	Р	Р		retain	canker
012	Fraxinus sp.	Ash	1	52	12	G	F	F		retain	
013	Fraxinus sp.	Ash	1	48	14	F	F	Р		retain	trunk w ound, poor form, broken branches, 30-40% deadw or
014	Fraxinus sp.	Ash	1	48	14	F	F	Р		retain	trunk w ound, poor form, broken branches, 30-40% deadw or
015	Fraxinus sp.	Ash	1	48	14	F	F	É		retain	poor form, outside of construction limit
016	Picea glauca	Colorado Spruce	1	28	12	D	D	D		retain	dead, outside of constructon limit
017	Picea glauca	Colorado Spruce	1	32	12	F	Р	Р		retain	50% deadw ood, outside of construction limt
018	Picea glauca	Colorado Spruce	1	32	12	Р	Р	Р		retain	30% deadw ood
019	Acer rubrum	Red Maple	1	14	7	F	F	F		retain	trunk giirdle (due to pow er trimmers)
020	Acer rubrum	Red Maple	1	37	12	G	G	G		retain	
021	Acer saccharum	Sugar Maple	1	12,15		Р	F	F		retain	multi-stem
023	Acer rubrum	Red Maple	1	15		Р	F	F		retain	major trunk w ound, exposed cambium, 20% deadw ood
G-025	GroupingAcer platanoides	Norway Maple	7	15-35		G-F	G-F	G-F		retain	exposed roots, damage from mow ers, 10-15% deadw ood, form, w eak unions

PLANT LIST - L1

Key	Qty.	Botanical Name	Common Name	Size	Condition	Remarks
Trees						
Deciduous						
Ar	4	Acer rubrum	Red Maple	45mm Cal	W.B	
As	3	Acer saccharum	Sugar Maple	45mm Cal	W.B	

Note: Each shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.





ISSUES/REVISIONS

ENGINEERING SERVICES

YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN TREE INVENTORY AND LANDSCAPE RESTORATION




100 Commerce Valley Dr. West, Thornhill, ON Canada L3T 0A1 t: 905.882.1100 f: 905.882.0055 www.mmm.ca



LEGENI) NATIVE UPLAND	SCALES: HOR: <u>1:500</u>	VER:		
+ + + + + + + + + + + + + + + + + + + +	FORAGE AND MEADOW MIX REFER TO DETAIL 6/L17	DATE DRAWN: AUGUST 2013			
* * * *	SODDING AREA FOR BOULEVARD AREA	DRAWN BY: JJ.Z	ED BY: P.M.		
	SODDING AREA FOR SPORTS FIELD	CONSULTANT DRAWING No.			
	SAND AREA FOR VOLLEYBALL COURT REFER TO DETAIL 1/L18	CITY CONTRACT No. 12-145			
	ASPHALT PATHWAY REPLACEMENT REFER TO DETAIL 2/L18	CITY REFERENCE No. R			

REFER TO SHEET L14, L15, L 16, L17, AND L18 FOR LANDSCAPE NOTES, DETAILS AND MASTER PLANT LIST.

- CONTRACTOR TO CONTACT THE CONTRACT ADMINISTRATOR FOR EXACT LOCATION PRIOR TO INSTALLATION OF TREES, SEEDING AND SODDING AREAS.
- ALL TREES ON SLOPED AREAS THAT MAY BE IMPACTED BY WATERMAIN CONSTRUCTION SHOULD BE REMOVED AND REPLACED WITH NEW TREES FOLLOWING WATERMAIN INSTALLATION.
- CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ANY DAMAGED SIGNS




TREE INVENTORY CHART -- TABLE 1

Project:	Guelph Trunk Sewer 10-12-108		Field Work Completed By: Ben Tymchyshyn								
Date of Fi	ield Work: 12/19/2012		Weather:								Conditions: G - Good, F - Fair, P - Poor, D - Dead
Tree ID	Botanical Name	Common Name	No.	DBH (cm)	Height (m)		Condition		Dripline	Recommendation	Remarks
#						Trunk	Canopy	Vigour	Radius		
G-022	Grouping–Picea glauca	Colorado Spruce	3	31,35	10	G	G	G		retain	group of 3. Note: One is leaning
024	Acer saccharum	Sugar Maple	1	30		G	G	G		retain	
026	Acer saccharum	Sugar Maple	1	18		G	G	G		retain	
027	Acer platanoides	Norway Maple	1	32		G	G	G		retain	
028	Pinus nigra	Austrian Pine	1	25	12	G	G	G		retain	
029	Ulmus pumila	Siberian Elm	1	26,38		G	G	G		retain	multi-stem
029(A)	Prunus sp.	Cherry	1	30		F	F	F		retain	
029(B)	Acersp.	Maple	1	40		F	F	F		retain	
032	Acer saccharum	Sugar Maple	1	55		G	G	G		retain	

PLANT LIST - L2

Key	Qty.	Botanical Name	Common Name	Size	Condition	Remarks
Trees						
Deciduous						
Ar	2	Acer rubrum	Red Maple	45mm Cal	W.B	
As	3	Acer saccharum	Sugar Maple	45mm Cal	W.B	
Qa	3	Quercus alba	White Oak	45mm Cal	W.B	
Qr	3	Quercus rubra	Red Oak	45mm Cal	W.B	
Shrubs						
cs	10	Cornus sericea	Red Osier Dogwood	50cm, 3gal.	pot	1.5m o.c.
ро	10	Physocarpus opulifolius	Eastern Ninebark	50cm, 3gal.	pot	1.5m o.c.
sc	10	Sambucus nigra ssp. canadensis	Common Elderberry	50cm, 3gal.	pot	1.5m o.c.
se	10	Salix eriocephala	Heart-leaved Willow	50cm, 3gal.	pot	1.5m o.c.

Note: Each shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.





ENGINEERING SERVICES

YORK TRUNK SEWER


PAISLEY-CLYTHE WATERMAIN TREE INVENTORY AND LANDSCAPE RESTORATION



100 Commerce Valley Dr. West, Thornhill, ON Canada L3T 0A1 t: 905.882.1100 f: 905.882.0055 www.mmm.ca




LEGENE)	SCALES: HOR: 1:500 VER:					
[+ + + +]	NATIVE UPLAND FORAGE AND	HOR: 1:500	VEN				
+ + + + +	MEADOW MIX REFER TO DETAIL 6/L17	DATE DRAWN: AUGUST 2013					
	SODDING AREA FOR	DRAWN BY:	CHECK	ED BY:			
* * * * * *	BOULEVARD AREA	JJ.Z	B.T./F	P.M.			
	SODDING AREA FOR SPORTS FIELD	CONSULTANT DRAWING No.					
	SAND AREA FOR						
	VOLLEYBALL COURT REFER TO DETAIL 1/L18	CITY CONTRAC 12-1					
	ASPHALT PATHWAY REPLACEMENT REFER TO DETAIL 2/L18	CITY REFEREN	CE No.	REV.			




NOTE:

• REFER TO SHEET L14, L15, L 16, L17, AND L18 FOR LANDSCAPE NOTES, DETAILS AND MASTER PLANT LIST.

- CONTRACTOR TO CONTACT THE CONTRACT ADMINISTRATOR FOR EXACT LOCATION PRIOR TO INSTALLATION OF TREES, SEEDING AND SODDING AREAS.
- ALL TREES ON SLOPED AREAS THAT MAY BE IMPACTED BY WATERMAIN CONSTRUCTION SHOULD BE REMOVED AND REPLACED WITH NEW TREES FOLLOWING WATERMAIN INSTALLATION.
- CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ANY DAMAGED SIGNS






TREE INVENTORY CHART -- TABLE 1

Project:	Guelph Trunk Sewer 10-12-108		Field Wor	k Complete	d By: Ben	Tymchysh	yn				
	ield Work: 12/19/2012		Weather:								Conditions: G - Good, F - Fair, P - Poor, D - Dead
	Botanical Name	Common Name	No.	DBH (cm)	Height (m)		Condition		Dripline	Recommendation	Remarks
#						Trunk	Canopy	Vigour	Radius		
064	Platanus x acerifolia	London Plane Tree	1	74		G	G	G		retain	root system may be imapcted and root pruning may be required
065	Quercus rubra	Red Oak	1	50		G	G	G		retain	
066	Populus deltoides	Eastem Cottonwood	1	78		G	G	G		retain	
066(A)	Acer sp.	Maple	1	<10		F	F	F		retain	
066(B)	Acer sp.	Maple	1	<10		F	F	F		retain	
066(C)	Acer sp.	Maple	1	<10		F	F	F		retain	
066(D)	Platanus x acerifolia	London Plane Tree	1	<10		F	F	F		retain	
067	Acer platanoides	Norway Maple	1	42		G	G	G		remove	w ill need to be removed due to the construction limits
068	Gleditsia triacanthos var. inermis	Thomless Honey Locust	1	35		G	G	G		retain	
069	Picea abies	Norway Spruce	1	50		G	G	G		retain	

PLANT LIST - L4

Key	Key Qty. Botanical Name		Common Name	Size	Condition	Remarks
Trees	Trees					
Deciduous						
Ar	5	Acer rubrum	Red Maple	45mm Cal	W.B	
As	11	Acer saccharum	Sugar Maple	45mm Cal	W.B	
Asa	3	Acer saccharinum	Silver Maple	45mm Cal	W.B	
Qa	3	Quercus alba	White Oak	45mm Cal	W.B	
Qr	8	Quercus rubra	Red Oak	45mm Cal	W.B	

Note: Each shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.



LEGEND

NATIVE UPLAND
FORAGE AND
MEADOW MIX REFER

TO DETAIL 6/L17

SODDING AREA FOR

BOULEVARD AREA

SODDING AREA FOR

SPORTS FIELD
SAND AREA FOR
VOLLEYBALL COURT
REFER TO DETAIL

ASPHALT PATHWAY
REPLACEMENT

REFER TO DETAIL 2/L18 HOR: 1:500 VER: _

AUGUST 2013

DRAWN BY: CHECKED BY


CONSULTANT DRAWING No.

CITY REFERENCE No. | REV.

CITY CONTRACT No.

B.T./P.M.


DATE DRAWN:



CONTRACTOR TO CONTACT THE CONTRACT ADMINISTRATOR FOR EXACT LOCATION PRIOR TO INSTALLATION OF

TREES, SEEDING AND SODDING AREAS.

- ALL TREES ON SLOPED AREAS THAT MAY BE IMPACTED BY WATERMAIN CONSTRUCTION SHOULD BE REMOVED AND REPLACED WITH NEW TREES FOLLOWING WATERMAIN INSTALLATION.
- CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ANY DAMAGED SIGNS




TREE INVENTORY CHART -- TABLE 1

Project: (Guelph Trunk Sewer 10-12-108		Field Wo	rk Complete	d By: Ben	Tym chysh	yn					Pro
Date of Fi	ield Work: 12/19/2012		Weather:								Conditions: G - Good, F - Fair, P - Poor, D - Dead	Dat
	Botanical Name	Common Name	No.	DBH (cm)	Height (m)		Condition		Dripline	Recommendation	Remarks	Tr
#						Trunk	Canopy	Vigour	Radius			
070	Pinus sylvestris	Scots Pine	1	19,20,22		G	F	F		retain	co-dominant stems, poor form, 10-20% deadw ood	
071	Pinus sylvestris	Scots Pine	1	20,23		G	F	F		retain	co-dominant stems, poor form, 10-20% deadw ood	
072	Gleditsia triacanthos var. inermis	Thomless Honey Locust	1	35		G	F	G		retain	poor form, outside of construction limit	
073	Gleditsia triacanthos var. inermis	Thomless Honey Locust	1	36		G	G	G		retain	epicormic grow th	
074	Gleditsia triacanthos var. inermis	Thomless Honey Locust	1	43		G	G	G		retain	10-20% deadw ood	
075	Gleditsia triacanthos var. inermis	Thomless Honey Locust	1	64		G	G	G		retain	10-20% deadw ood	
076	Prunus sp.	Cherry	1	26,23,15		F	F	G		rem ove	suckers, poor form, multi-stem, epicormic growth, 10-15% deadw ood	
077	Prunus sp.	Cherry	1	24,21,20		F	F	G		remove	suckers, poor form, multi-stem, epicormic growth, 10-15% deadw ood, will need to be removed due to the construction limits	
078	Prunus sp.	Cherry	1	21/21/20		F	F	G		rem ove	suckers, poor form, multi-stem, epicormic growth, 10-15% deadw ood, will need to be removed due to the construction limits	\parallel
079	Prunus sp.	Cherry	1	21,18,24,14		F	F	G		retain	suckers, poor form, multi-stem, epicormic growth, 10-15% deadw ood	
080	Quercus rubra	Red Oak	1	15		G	G	G		retain		
081	Acer platanoides	Norway Maple	1	46		G	G	G		retain	girdling roots	
082	Acer platanoides	Norway Maple	1	42		G	G	G		retain		
083	Acer platanoides	Norway Maple	1	44		G	G	G		retain	girdling roots	
084	Acer platanoides	Norway Maple	1	28		G	G	G		retain		
085	Acer platanoides	Norway Maple	1	38		G	G	G		retain		
086	Acer platanoides	Norway Maple	1	56		G	G	G		retain		
087	Tilia americana	Basswood	1	50		D	D	D		retain	dead, outside of constructon limit	
088	Prunus sp.	Cherry	1	19/22/24		Р	Р	Р		retain	multi-stem	_
089	Malus sp.	Crabapple	1	27/22		G	G	G		retain	multi-stem	

_												
\dashv		Guelph Trunk Sewer 10-12-108 eld Work: 12/19/2012		Weather:	k Complete	d By: Ben	Tym chysh	/n				Conditions: G - Good, F - Fair, P - Poor, D - Dead
\dashv		Botanical Name	Common Name	No.		Height (m)		Condition		Dripline	Recommendation	Remarks
	#	Dotalical Name	Common Name	140.	DDIT (CIII)	rieight (iii)	Trunk	Canopy	Vigour	Radius		Kellarks
	090	Salix alba 'Tristis'	Golden Weeping Willow	1	84/84		Р	F	G		retain	multi-stem, large w ound, w eakly formed union, broken branches, poor form
	091	stuck to #092									retain	
	092	Fraxinus pennsylvanica	Red Ash	1	13		G	G	G		retain	
	093	Acer platanoides	Norway Maple	1	38		Р	F	G		retain	large w ound, contorted grow th
	094	Salix sp.	Willow	1	74		G	G	G		retain	
	095	Fraxinus sp.	Ash	1	12		G	G	G		retain	
	096	Fraxinus sp.	Ash	1	12		G	G	G		retain	
nits	097	Salix sp.	Willow	1	121		Р	G	G		retain	large w ound, broken branch exposed
	098	Acer platanoides	Norway Maple	1	39		G	G	G		retain	
nits	099	Fraxinus sp.	Ash	1	11		F	G	G		retain	trunk w ound
	100	Salix sp.	Willow	1	84		F	G	G		retain	evidence of torsion on trunk
	101	Salix sp.	Willow	1	88		G	G	G		retain	
	102	Salix sp.	Willow	1	69		G	G	G		retain	
	103	Fraxinus sp.	Ash	1	10		G	G	G		retain	
_	104	Acer platanoides	Norway Maple	1	38		G	G	G		retain	
	105	Fraxinus sp.	Ash	1	15		G	G	G		retain	
4	106	Acer platanoides	Norway Maple	1	65		G	G	G		retain	
4	107	Picea glauca	White Spruce	1	14		G	G	G		retain	
_	108	Betula papyrifera	White Birch	1	40		F	G	G		retain	

PLANT LIST - L5

Key	Qty.	Botanical Name	Common Name	Size	Condition	Remarks		
Trees								
Deciduous								
As	4	Acer saccharum	Sugar Maple	45mm Cal	W.B			
Qr	4	Quercus rubra	Red Oak	45mm Cal	W.B			
Note: Fach shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.								



IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUPING TO REMAIN REFER TO TABLE 1 (L1 TO L11) FOR TREE INVENTORY CHART

IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUPING TO REMAIN REFER TO TABLE 2 (L12) FOR TREE INVENTORY

IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUPING TO REMAIN REFER TO TABLE 3 (L7) FOR TREE INVENTORY

TREE PROTECTION FENCING REFER TO DETAIL 1/L16 AND 2/L16

TREE PROTECTION FENCE WITH EROSION CONTROL. REFER TO DETAIL 1/L16

		8888	DETAIL 3/L18	ENI KEFE	:K 10
	2	JAN 23, 14	GRCA SUBMISSION	JJZ	ВТ
	1	OCT 25, 13	FINAL ARBORIST REPORT	JJZ	BT/PM
	No.	DATE	DESCRIPTION	BY:	CH'KD.
_			ISSUES/REVISIONS	 S	



ENGINEERING SERVICES


YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN TREE INVENTORY AND LANDSCAPE RESTORATION






GENE)	SCALES:						
*	NATIVE UPLAND FORAGE AND MEADOW MIX REFER TO DETAIL 6/L17	DATE DRAWN: AUGUS	VER:					
* * * *	SODDING AREA FOR BOULEVARD AREA	DRAWN BY: JJ.Z	CHECKI B.T./F					
	SODDING AREA FOR SPORTS FIELD	CONSULTANT I		S No.				
	SAND AREA FOR VOLLEYBALL COURT REFER TO DETAIL 1/L18	CITY CONTRAC						
	ASPHALT PATHWAY REPLACEMENT REFER TO DETAIL	CITY REFEREN	CE No.	REV.				



CONSTRUCTION SHOULD BE REMOVED AND REPLACED WITH NEW TREES FOLLOWING WATERMAIN INSTALLATION.

CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ANY DAMAGED SIGNS




TREE INVENTORY CHART -- TABLE 1


	Guelph Trunk Sewer 10-12-108			rk Complete	d By: Ben	Гутсhуsh	yn				
	eld Work: 12/19/2012		Weather								Conditions: G - Good, F - Fair, P - Poor, D - Dead
	Botanical Name	Common Name	No.	DBH (cm)	Height (m)				Dripline	Recommendation	Remarks
#						Trunk	Canopy	Vigour	Radius		
109	Betula papyrifera	White Birch	1	48		F	G	G		retain	
110	Prunus sp.	Cherry	1	32		F	F	F		retain	w eakly formed union, poor form, exposed cambium
111	Acer platanoides	Norway Maple	1	38		G	F	G		retain	w eakly formed union
112	Acer platanoides	Norway Maple	1	26		Р	F	Р		retain	stem w ounds, 20-30% deadw ood, trunk w ound
113	Acer platanoides	Norway Maple	1	49		G	F	G		retain	w eakly formed union
114	Aesculus hippocastanum	Horsechestnut	1	60		F	F	G		retain	trunk torsion, poor form, trunk w ound
115	Aesculus hippocastanum	Horsechestnut	1	99		Р	F	F		retain	poor form, wealky formed unions, included bark crack, decay, 1 15% deadwood
119	Acer platanoides	Norway Maple	1	42		F	F	F		retain	cracked tree, dead branches
120	Acer platanoides	Norway Maple	1	48		G	F	F		remove	poor pruning practices, 10-15% deadwood, poor form, may nee to be removed due to the construction limits

PLANT LIST - L6


Key	Qty.	Botanical Name	Common Name	Size	Condition	Remarks
Trees						
Deciduous						
Qa	5	Quercus alba	White Oak	45mm Cal	W.B	
Qr	3	Quercus rubra	Red Oak	45mm Cal	W.B.	
Shrubs						
CS	10	Cornus sericea	Red Osier Dogwood	50cm, 3gal.	pot	1.5m o.c.
ро	10	Physocarpus opulifolius	Eastern Ninebark	50cm, 3gal.	pot	1.5m o.c.
SC	10	Sambucus nigra ssp. canadensis	Common Elderberry	50cm, 3gal.	pot	1.5m o.c.
se	10	Salix eriocephala	Heart-leaved Willow	50cm, 3gal.	pot	1.5m o.c.

Note: Each shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.





- CONTRACTOR TO CONTACT THE CONTRACT ADMINISTRATOR FOR EXACT LOCATION PRIOR TO INSTALLATION OF TREES, SEEDING AND SODDING AREAS.
- ALL TREES ON SLOPED AREAS THAT MAY BE IMPACTED BY WATERMAIN CONSTRUCTION SHOULD BE REMOVED AND REPLACED WITH NEW TREES FOLLOWING WATERMAIN INSTALLATION.
- CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ANY DAMAGED SIGNS



TREE INVENTORY CHART -- TABLE 1

G-140A Grouping--Acer saccharinum

Silver Maple

	Guelph Trunk Sewer 10-12-108			rk Complete	d By: Ben	lym chysh	yn				
	ield Work: 12/19/2012		Weather								Conditions: G - Good, F - Fair, P - Poor, D - Dead
Tree ID	Botanical Name	Common Name	No.	DBH (cm)	Height (m)	Trunk	Condition	Vigour	Dripline Radius	Recommendation	Remarks
116	Acer platanoides	Norway Maple	1	45		G	G	G	rtuuuo	remove	
117	Acer platanoides	Norway Maple	1	51		F	F	G		William Addressed in the	poor form, broken branches, 10-% deadw ood, trunk deformit
118	Acer platanoides	Norway Maple	1	35		F	F	F		remove	lean, dead branches, 15% deadw ood, exposed cambium on
121	Fraxinus sp.	Ash	1	69		G	G	F		retain	upper stems 10% deadw ood
122	Fraxinus sp.	Ash	1	41		F	G	G		retain	10-15% deadw ood, lean
123	Tilia cordata	Little-leaf Linden	1	69		F	G	G		retain	lean
124	Tilia cordata	Little-leaf Linden	1	60		F	F	G		retain	w eakly formed union, included bark
125	Gleditsia triacanthos	Honeylocust	1	50		F	G	G		retain	10-15% deadw ood
126	Gleditsia triacanthos	Honeylocust	1	44		G	G	G		retain	10-15% deadw ood
127	Sorbus aucuparia	European Mountain Ash	1	23		G	F	G		retain	w eakly formed union
128	Sorbus aucuparia	European Mountain Ash	1	23		G	G	G		retain	slight lean, 10% deadw ood
129	Fraxinus pennsylvanica	Green Ash	1	63		Р	G	G		retain	Manitoba Maple beside acer negundo. Wound, cavity
130	Juglans nigra	Black Walnut	1	12		G	G	G		retain	
G-131	Juglans nigra	Black Walnut	2	22/11		G	G	G		retain	2 trees
132	Pinus nigra	Austrian Pine	1	24	6	Р	Р	Р		retain	note: a lot of sumac underbrush around pines, Tilia 0.5m from
133	Pinus nigra	Austrian Pine	1	29	7	G	G	G		retain	multi-stem Tilia grow ing w /n 0.5m of Pine
134	Pinus nigra	Austrian Pine	1	27	7	Р	Р	Р		retain	
135	Populus tremuloides	Trembling Aspen	1	96		P	F	F		retain	a lot of trunk damage
G-136	GroupingFraxinus sp.	Ash	7	12		G	G	G		retain/remove	1 small Ash, 6 small Maples in surrounding area - under 10 m inside of grading limit
137	Acer saccharinum	Silver Maple	1	12		G	G	G		retain	2 other small Maples in surrounding area under 10 mm
138	Acer saccharinum	Silver Maple	1	37		G	G	G		retain	
G-139	Grouping-Juglans nigra	Black Walnut	1	10		G	G	G		retain/remove	6 small caliper trees
140	Salix sp.	Willow	1	131		Р	F	Р		retain	large broken branches
0 1101	Communication Annual Control of the	Cilver Menle	_	40.05		0.5	0.5	0			multi-stem, poor form, unions. Opposite side of trail from 140,

G-F G-F G


5 10-25

ΓR	EE INVENTORY	CHA	RT		TA	BL	.E :	3						
Tree No.	Tree Species	ОВН (ст)	Crown Reserve (m)	Biological Health (H,M,L)	Structural Condition (H,M,L)	Age Category* (see below)	Life Expectancy** (see below)	Height (metres)	Municipal Tree	Off-site Tree	Rec. Action Based on Condition	Rec. Action Based on Construction Impacts	Final Recommendation	Observations / Comments
10	Quercus rubra Red Oak	25	11	Н	Н	3	6	7.3	0	0	Р	Р	Р	LC (M), leaf necrosis (L)
11	Acer platanoides Norway Maple	18	8	Н	Н	2	6	7.1	0	0	Р	Р	Р	Memorial tree
12	Acer platanoides Norway Maple	36	12	Н	М	4	6	8.9	0	0	Р	Р	Р	Poorly formed buttress (M)
13	Juglans nigra Black Walnut	8	6	Н	M(L)	1	4	3	0	1	Р	Р	Р	CU(H-N,S)
14	Pyrus communis Pear	8,7	5	Н	М	1	5	3.5	0	0	Р	R	R	
15	Pyrus communis Pear	5,3	3	Н	М	1	5	2.9	0	1	Р	Р	Р	
16	Acer negundo Manitoba Maple	18,9	10	Н	М	2	5	8.6	0	1	Р	Р	Р	Many large laterals low on trunk
17	Acer negundo Manitoba Maple	19	9	Н	М	2	5	8.6	0	1	Р	Р	Р	3 large basal sprouts
18	Populus deltoides ssp. deltoides Eastern Cottonw ood	78	16	Н	М	5	3	17	0	1	Р	Р	Р	CU(M-SE)
19	Juglans nigra Black Walnut	14	7	Н	H(M)	2	6	7.5	0	1	Р	Р	Р	Open grown form
20	Acer negundo Manitoba Maple	18,17, 14,15,17	14	Н	М	2	5	7.8	0	1	Р	Р	Р	
21	Juglans nigra Black Walnut	6	3	Н	L	1	2	3.5	0	0	Р	Р	Р	LP(H)
22	Pinus nigra Austrian Pine	30	10	H(M)	М	2	5	8.7	0	0	Р	Р	Р	
23	Tilia cordata Little-leaf Linden	11,11	8	H(M)	М	2	6	8.7	0	0	P	Р	Р	
24	Pinus nigra Austrian Pine	25	8	H(M)	М	3	5	8	0	0	Р	Р	Р	Growing in thicket, tree tag #132

THE FIELD WORK OF TREE SPECIES LISTED UNDER THE TREE INVENTORY TABLE 3 WAS COMPLETED BY ABOUD & ASSOCIATES INC. REFER TO THE ABOUD & ASSOCIATES INC.'S ROAD AND SERVICE IMPROVEMENTS WELLINGTON STREET ARBORIST REPORT, NOVEMBER 12, 2013 FOR DETAILS

PLANT LIST - L7

Key	Qty.	Botanical Name	Common Name	Size	Condition	Remarks
Trees						
Deciduous						
Ar	3	Acer rubrum	Red Maple	45mm Cal	W.B	
As	9	Acer saccharum	Sugar Maple	45mm Cal	W.B	
Asa	4	Acer saccharinum	Silver Maple	45mm Cal	W.B	
Jn	9	Juglans nigra	Black Walnut	45mm Cal	W.B	
Qa	6	Quercus alba	White Oak	45mm Cal	W.B	
Qr	6	Quercus rubra	Red Oak	45mm Cal	W.B	
Coniferous						
Pg	3	Picea glauca	White Spruce	200cm ht	W.B	
Ps	6	Pinus strobus	Eastern White Pine	200cm ht	W.B	



PROPOSED DECIDUOUS AND CONIFEROUS TREES REFER TO DETAIL 1/L17, 2/L17, PROPOSED SHRUBS REFER TO DETAIL 4/L17

APPROXIMATE LOCATION OF TRANSPLANTED TREES REFER TO DETAIL 3/L16 AND 4/L16

EXISTING SURVEYED TREES

EXISTING TREE GROUPING EXISTING TREE GROUP/ WOODLOT TO BE

> EXISTING TREE GROUP/ WOODLOT TO BE TRANSPLANTED. REFER TO DETAIL 3/L16 AND 4/L16

EXISTING TREE TO BE REMOVED LIMIT OF WORK

Asa SPECIES PLANT KEY FOR LANDSCAPE RESTORATION
3 QUANTITY REFER TO L17 FOR MASTER PLAN LIST

PLANT KEY FOR EXISTING TREES TO BE TRANSPLANTED, REFER TO TREE
INVENTORY/MANAGEMENT PLAN L11 FOR EXISTING TREE LOCATION

> IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUP TO BE REMOVED IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUPING TO REMAIN REFER TO TABLE 1 (L1 TO L11) FOR TREE INVENTORY CHART

IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUPING TO REMAIN REFER TO TABLE 2 (L12) FOR TREE INVENTORY

IDENTIFICATION NUMBER FOR EXISTING INDIVIDUAL TREE OR GROUPING TO REMAIN REFER TO TABLE 3 (L7) FOR TREE INVENTORY

TREE PROTECTION FENCING REFER TO DETAIL 1/L16 AND 2/L16

TREE PROTECTION FENCE WITH EROSION CONTROL. REFER TO DETAIL 1/L16

		LIMESTONE TRAIL REPLACEM DETAIL 3/L18	ENT REFE	R TO
2	JAN 23, 14	GRCA SUBMISSION	JJZ	ВТ
1	OCT 25, 13	FINAL ARBORIST REPORT	JJZ	BT/PM
No.	DATE	DESCRIPTION	BY:	CH'KD


ISSUES/REVISIONS

ENGINEERING SERVICES

YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN TREE INVENTORY AND LANDSCAPE RESTORATION







LEGEND	
+ + + + + + + + + + + +	NATIVE UPLAND FORAGE AND MEADOW MIX REI TO DETAIL 6/L17
* * * * *	SODDING AREA F BOULEVARD AREA
(///////	SODDING AREA E


SPORTS FIELD SAND AREA FOR VOLLEYBALL COURT REFER TO DETAIL


AUGUST 2013 DRAWN BY: CHECKED BY B.T./P.M. CONSULTANT DRAWING No.

DATE DRAWN:

CITY CONTRACT No. CITY REFERENCE No. REV.

ASPHALT PATHWAY
REPLACEMENT REFER TO DETAIL





1023 Acer saccharinum

1024 Acer saccharinum

Silver Maple

Silver Maple

2

1 98

F

G

retain

retain

10

Quercus rubra

Red Oak

Note: Each shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.

W.B


ASPHALT PATHWAY
REPLACEMENT

REFER TO DETAIL

CITY REFERENCE No. | REV.

ROYAL CITY PARK AREA -- TREE INVENTORY CHART -- TABLE 1, REFER TO SHEET L9 FOR TREE INVENTORY PLAN

Project: Guelph Trunk Sewer 10-12-108			rk Completed By: Ben	Tymchysh	yn						t: Guelph Trunk Sewer 10-12-108				I By: Ben Tymchysh	yn				
Date of Field Work: 12/19/2012 Tree ID Botanical Name	Common Name	Weather: No.	DBH (cm) Height (m)		Condition		Dripline	Re com m e ndation	Conditions: G - Good, F - Fair, P - Poor, D - Dead Remarks		f Field Work: 12/19/2012 D Botanical Name	Common Name	Weather: No.	DBH (cm)	Height (m)	Condition		Dripline	Recommendation	Conditions: G - Good, F - Fair, P - Poor, D - Dead Remarks
#					Canopy	Vigour	Radius			#						Canopy	Vigour	Radius		
169 Acer platanoides	Maple	1	72	G	G	G		retain		274	Acer platanoides	Norway Maple	1	73	F	F	F	8	retain	mature
170 Acer platanoides	Maple	1	85	G	G	G		retain	A- 8 mm Mpale, B - 8 mm Maple, C - 8 mm Maple	275	Acer saccharum	Sugar Maple	1	6	F	G	G	1	retain	young
G-171 Acer platanoides	Maple	4	45	Р	Р	Р		retain	tw o large trunk scars, 3 small caliper trees beside	276	Acer platanoides	Norway Maple	1	56	F	G	G	10	retain	mature
234 Acer platanoides	Norway Maple	1	41	F	Р	Р	4	retain	semi-mature	277	Acer platanoides	Norway Maple	1	68	Р	F	F	10	retain	mature
235 Acer platanoides	Norway Maple	1	48	G	F	F	4	retain	semi-mature	278	Acer saccharinum	Silver Maple	1	125	F	G	F	10	remove	mature, tree w as part of inventory, but has since been removed due to 2013 w inter ice storm damage
236 Acer platanoides	Norway Maple	1	65	Р	F	Р	4	retain	mature	279	Gleditsia triacanthos	Honey Locust	1	41	G	G	G	8	remove	semi-mature, tree w as part of inventory, but has since been removed due to 2013 w inter ice storm damage
238 Fraxinus americana	White Ash	1	70	G	F	F	10	retain	mature	280	Quercus rubra	Red Oak	1	22	F	G	G	4	retain	semi-mature
240 Fraxinus pennsylvanica	Green Ash	1	62	G	G	F	6	retain	mature	281	Acer saccharum	Sugar Maple	1	15	F	G	G	1	retain	young
242 Picea glauca	W ite Spruce	1	27	G	G	G	3	retain	semi-mature	284	Acer platanoides	Norway Maple	1	94	F	F	F	10	retain	mature
243 Fraxinus americana	White Ash	1	56	G	F	F	6	retain	mature	285	Acer platanoides	Norway Maple	1	26	G	G	G	4	retain	semi-mature
244 Fraxinus americana	White Ash	1	75	G	G	G	10	retain	mature	286	Acer platanoides	Norway Maple	1	78	G	G	G	10	retain	mature
245 Fraxinus pennsylvanica	Green Ash	1	17	G	G	G	1	retain	young	287	Acer platanoides	Norway Maple	1	56	G	G	G	6	retain	mature
246 Picea glauca	White Spruce	1	46	G	G	G	4	retain	semi-mature	288	Acer platanoides	Norway Maple	1	46	G	G	G	5	retain	semi-mature
246A Refer to Mark-Up of Royal City Par	k Plan for the location of the followin	g trees (asso	ociated with tag #246)					retain		289	Acer platanoides	Norway Maple	1	15	G	G	G	3	retain	young
A Platanus x acerifolia	London Plane Tree	1	9	G	G	G		retain		290	Acer platanoides	Norway Maple	1	17	G	G	G	2	retain	young
B Tilia americana	Basswood	1	9	G	G	G		retain		291	Acer saccharinum	Silver Maple	1	107	G	G	G	10	remove	mature, tree w as part of inventory, but has since been removed due to 2013 w inter ice storm damage
C Liriodendron tulipifera	Tulip Tree	1	8	G	G	G		retain		G-292	2 Acer platanoides	Norway Maple (clump of 3)	3	19	G	G	G	3	retain	young, 2 Maple, 1 Ash
D Quercus rubrum	Red Oak	1	4	G	G	G		retain		293	Quercus rubra	Red Oak	1	10	F	G	F	2	retain	young
247 Fraxinus americana	White Ash	1	74	G	F	F	10	retain	mature	1	Acer platanoides	Norway Maple	1	18	G	G	G	2	retain	semi-mature
248 Fraxinus americana	White Ash	1	57	G	F	F	6	retain	mature	295		Sugar Maple	1	36	G	G	G	6	retain	semi-mature
249 Picea glauca	White Spruce	1	25	G	F	F	3	retain	semi-mature	296		White Cedar	1	19	G	G	G	2	retain	semi-mature
251 Fraxinus americana	White Ash	1	55	F	F	F	7	retain	mature	297	-	White Cedar	1	26	G	G	G	3	retain	semi-mature
252 Picea glauca	White Spruce	1	34	G	G	G	3	retain	semi-mature	298		Blue spruce	1	38	G	G	G	3	retain	semi-mature
252 (A) Carpinus caroliniana	Blue Beech	1	6	G	G	G	3	retain	young	299		White Cedar	1	18	G	G	G	3	retain	semi-mature
252 (B) Tilia americana		1	5	G	G	G				300		White Cedar	1	24	G	G	G	2	retain	semi-mature
	Basswood	1	122		-	-	10	retain	young	╢	-		1					40		
253 Acer saccharinum	Silver Maple	1	133	G	-	-	10	retain	mature	301		Norway Maple	1	91	G	G	G	10	retain	mature
254 Acer platanoides	Norway Maple	1	29	G	G	G	4	retain	semi-mature	303		Silver Maple	1	99		G	-	10	retain	mature
255 Juglans cinerea	Buttemut	1	100	P	-	Р _	8	retain	mature	+	Picea glauca	White Spruce	1	32	G	G	G	2	retain	semi-mature
256 Fraxinus americana	White Ash	1	59	F	F	F	8	retain	mature	$\{ \mid \mid$	Picea glauca	White Spruce	1	37	G	G	G	2	retain	semi-mature
257 Picea glauca	White Spruce	1	25	G	G	G	3	retain	semi-mature	+	Pinus nigra	Austrian Pine	1	32	G	G	G	3	retain	semi-mature
258 Acer saccharinum	Silver Maple	1	165	F	F	F	10	retain	mature, *Hazard Tree*	+	Picea pungens	Blue spruce	1	21	G	G	G	2	retain	semi-mature
259 Pinus sylvestris	Scots pine	1	20	Р	F	F	2	retain	young	┨	Picea pungens	Blue spruce	1	32	G	G	G	3	retain	semi-mature
260 Acer saccharinum	Silver Maple	1	118	G	G	G	10	retain	mature	+	Picea pungens	Blue spruce	1	42	G	G	G	3	retain	semi-mature
261 Ulmus americana	American Elm	1	14	G	G	G	2	retain	semi-mature	┨├──	Taxus canadensis	Yew	1	24	G	G	G	5	retain	semi-mature
262 Acer saccharinum	Silver Maple	1	109	F	G	F	10	retain	mature	311		Blue spruce	1	24	G	F	G	3	retain	semi-mature
263 Acer platanoides	Norway Maple	1	22	G	G	G	3	retain	semi-mature	312	Tilia cordata	Little leaf Linden	1	35	G	G	G	6	retain	semi-mature
264 Acer platanoides	Norway Maple	1	14	G	G	G	3	retain	semi-mature	313	Picea glauca	White Spruce	1	26	G	G	G	3	retain	semi-mature
265 Acer platanoides	Norway Maple	1	15	G	G	G	3	retain	semi-mature	314	Picea glauca	White Spruce	1	21	G	G	G	3	retain	semi-mature
266 Acer platanoides	Norway Maple	1	14	G	G	G	3	retain	semi-mature	316	Fraxinus pennsylvanica	Green Ash	1	32	G	G	G	4	retain	semi-mature
267 Acer saccharinum	Silver Maple	1	109	F	F	F		retain	mature	317	Acer platanoides	Norway Maple	1	17	G	G	G	3	retain	semi-mature
268 Morus rubra	Mulberry	1	7	G	G	G	1	retain	young	G-317 ((A) Acer platanoides	Norway Maple (clump of 5)	5	10, 14, 22, 32, 46	G	G	G		retain	semi-mature
269 Pinus strobus	White Pine	1	25	F	F	F	5	retain	semi-mature	319	Acer saccharinum	Silver Maple	1	41	G	G	G	5	retain	semi-mature
270 Picea glauca	WhiteSpruce	1	40	G	G	G	6	retain	semi-mature	320	Acer saccharinum	Silver Maple	1	24	G	G	G	5	retain	semi-mature
271 Acer platanoides	Norway Maple	1	57	G	G	G	8	retain	mature	321	Acer saccharinum	Silver Maple	1	24	G	G	G	2	retain	semi-mature
272 Acer platanoides	Norway Maple	1	43	G	G	G	6	retain	mature	322	Acer platanoides	Norway Maple	1	58	G	Р	F	9	retain	mature
273 Acer saccharinum	Silver Maple	1	98	Р	F	F	10	retain	mature	323	Acer saccharinum	Silver Maple	1	32	G	G	G	4	retain	semi-mature
				L	J	L			I											



		ISSUES/REVISION:	 S	
No.	DATE	DESCRIPTION	BY:	CH'KD
1	OCT 25, 13	FINAL ARBORIST REPORT	JJZ	BT/PM
2	JAN 23, 14	GRCA SUBMISSION	JJZ	ВТ



ENGINEERING SERVICES


YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN TREE INVENTORY AND LANDSCAPE RESTORATION






SCALES: HOR: 1:500	VER:						
DATE DRAWN:	T 2012						
AUGUS	1 2013						
DRAWN BY:	CHECK	ED B					
JJ.Z B.T./P.							
CONSULTANT D	DRAWING	No.					
L1	0						
CITY CONTRAC	T No.						
12-1	45						
CITY REFEREN	CE No.	RE					



NEW TREES FOLLOWING


WATERMAIN INSTALLATION.





TREE INVENTORY CHART -- TABLE 1, REFER TO SHEET L12 FOR TREE INVENTORY CHART -- TABLE 2


Project:	Guelph Trunk Sewer 10-12-108		Field Wo	rk Complete	d By: Ben	Tym chysh	yn				
A MANAGEMENT OF THE PARTY OF TH	ield Work: 12/19/2012		Weather:								Conditions: G - Good, F - Fair, P - Poor, D - Dead
	Botanical Name	Common Name	No.	DBH (cm)	Height (m)		Condition		Dripline	Recommendation	Remarks
#						Trunk	Canopy	Vigour	Radius		
172	Salix sp.	Willow	1	140		Р	Р	Р		retain	
G-173	Grouping		30	22 avg.						retain	large massing - Manitoba Maples and Ash (30 trees)
G-174	Acer sp.	Maple	3	19		G	G	G		retain/transplant	A-8 mm Mpale, B-8 mm Maple, C-8 mm Maple tw o large trunk scars, 3 small caliper trees beside
175	Acer sp.	Maple	1	10		G	G	G		transplant	may need to be transplanted due to the construction limits
176	Acer platanoides	Norway Maple	1	10		G	G	G		transplant	w ill need to be transplanted due to the construction limits
177	Pinus strobus	White Pine	1	20		G	G	G		transplant	
178	Pinus strobus	White Pine	1	23		G	G	G		retain	
179	Pinus strobus	White Pine	1	23		G	G	G		retain	
G-180	Grouping-Thuja sp.	Cedar	3	14 avg.		Р	Р	Р		retain	grouping of 3 Cedars
G-181	Fraxinus sp.	Ash	12	21 avg.		G	G	G		retain	grouping of 12
G-182	Grouping-Acer negundo	Manitoba Maple	2	20 avg.		G	G	G		retain	grouping of 2, multi-stem
183	Acer negundo	Manitoba Maple	1	10-15		G	G	G		retain	multi-stem



TREE INVENTORY CHART -- TABLE 2, REFER TO SHEET L11 FOR TREE INVENTORY PLAN

Project: Guelph Trunk Sewer 10-12-108 Date of Field Work: June 18 2008 (Updated 10/10/2013)		Field Wo Weather:	rk Complete	d By: Silv-	Econ Ltd.	Group Ltd.) Conditions: G - Good, F - Fair, P - Poor, D - Dead	Pr Da					
	Botanical Name	Common Name	No.	DBH (cm)	Height (m)		Condition		Dripline	Recommendation	Remarks	1 7
#						Trunk	Canopy	Vigour	Radius			┧┞
201	Juglans nigra	Black Walnut	1	9		G	G	Р	3	retain	90% dead, outside construction limit	
202	Juglans nigra	Black Walnut	1	8		G	G	F	3	retain	20-30% dead	
203	Juglans nigra	Black Walnut	1	32		G	G	G	5	retain	10-15% dead	
204	Acernegundo	Manitoba Maple	1	49		G	G	G	5	retain	suckering @ base, tip die back	
205	Acer negundo	Manitoba Maple	1	33,52		F	F	Р	4.5	retain	30-40% deadw ood, multi-stem	
206	Juglans nigra	Black Walnut	1	22		G	G	Р	4	remove	80% deadw ood	
207	Juglans nigra	Black Walnut	1	25		G	G	Р	4	remove	80% deadw ood	
208	Juglans nigra	Black Walnut	1	19		G	G	Р	4	remove	60% deadw ood, vine in crow n	
209	Acer negundo	Manitoba Maple	1	10,14		F	F	G	4	remove	lean, poor form, vine in crow n, multi-stem	
210	Juniperus virginiana	Eastern Red Cedar	1	13	8	G	G	G	2.5	remove	10% die back in low er canopy, tree 212,213,214,215 associated with tree tag #210	
211	Juglans nigra	Black Walnut	1	26		G	G	G	6	remove	10-20% deadw ood	11
212	Juglans nigra	Black Walnut	1	14		G	G	Р	2.5	retain	80% deadw ood	11
213	Juglans nigra	Black Walnut	1	19		G	G	F	3	retain	10-25% deadw ood	$\ \cdot \ $
214	Juglans nigra	Black Walnut	1	13		G	G	Р	2.5	retain	90% deadw ood	1
215	Juglans nigra	Black Walnut	1	16.5		G	G	Р	2.5	retain	90% deadw ood, multi-stem	╟
216	Juglans nigra	Black Walnut	1	20		D	D	D	2.5	retain	dead, outside construction limit	$\ \cdot\ $
217	Juglans nigra	Black Walnut	1	24		G	G	Р	4	retain	90% deadw ood, outside construction limit]
218	Acer negundo	Manitoba Maple	1	11,13		F	F	G	4	retain	poor form, lean, multi-stem	╟
219	Acer negundo	Manitoba Maple	1	31,42		F	F	G	5	retain	vine in crow n, 10-20% dead, lean, conducted grow th, poor form, multi-stem	1
220	Ulmus sp.	Elm	1	51		G	G	G	7	retain		╟
221	Acer negundo	Manitoba Maple	1	22,16,21		F	F	G	4	retain	multi-stem, lean, poor form	1
222	Acer negundo	Manitoba Maple	1	25		Р	F	F		retain	80% lean, poor form, outside construction limit	1
223	Acer negundo	Manitoba Maple	1	36		F	F	F	4	retain	lean, poor form, vine in crow n, 20-25% dead wood	1
224	Acer negundo	Manitoba Maple	1	27		F	F	G	5	retain	lean, poor form, vine in crow n	1
225	Acer negundo	Manitoba Maple	1	24,38		F	F	G	8	retain	multi-stem, lean, poor form, vine in crow n	1
226	Acer platanoides	Norway Maple	1	20		G	G	F	4.5	retain	leaf scorch, suppressed from adjacent w illow	1
227	Acer negundo	Manitoba Maple	1	13,9,6		F	F	F	3.5	retain	multi-stem	1
228	Acer negundo	Manitoba Maple	1	14		F	F	G	7	retain	70% lean	1
229	Juglans nigra	Black Walnut	1	27		F	F	G	3.5	retain	conducted grow th, closed willow branch leaning on tree	1
230	Acer negundo	Manitoba Maple	1	12		F	F	G	3.5	retain	dead w illow branch leaning on tree, outside construction limit	1
231	Acer platanoides	Norway Maple	1	27		G	G	G	5	retain	tar spot	1

	Project: Guelph Trunk Sewer 10-12-108			Field Work Completed By: Silv-Econ Ltd. (Updated 10/10/2013 by Ben Tymchyshyn - MMM Group Ltd.)								Group Ltd.) Conditions: G - Good, F - Fair, P - Poor, D - Dear
+		Field Work: June 18 2008 (Updated 10/10/2013) D Botanical Name Common Name		26:55 at 18:00x 99:001 2:37							Remarks	
	#	Bota ilicar Naille	Common Name	NO.	DBH (CIII)	neight (III)	Trunk	Canopy	Vigour	Radius		Remarks
	232	Acer negundo	Manitoba Maple	1	11		G	G	G	3	retain	suppressed
	233	Acer platanoides	Norway Maple	1	12		F	G	G	3	retain	lean, suppressed
	234	Acer negundo	Manitoba Maple	1	16		F	F	G	3	remove	80% lean, poor form
	235	Acer negundo	Manitoba Maple	1	19,13		F	F	G	3	remove	multi-stem, 80% lean, poor form
	236	Acer negundo	Manitoba Maple	1	18,20		F	F	F	1	remove	multi-stem, 90% lean, poor form
	237	Acer platanoides	Norway Maple	1	19		G	G	G	3	remove	dead w illow branch leanning on tree
	238	Acer negundo	Manitoba Maple	1	15		G	G	Р	4	retain	80% deadw ood, outside construction limit
	239	Acer negundo	Manitoba Maple	1	15		F	F	G	3	retain	70% lean
	240	Acer negundo	Manitoba Maple	1	16,8,6		F	Р	G	4	retain	multi-stem
1	241	Acer platanoides	Norway Maple	1	19		G	G	G	3.5	retain	
	242	Acer platanoides	Norway Maple	1	16		G	G	G	3.5	retain	
$\ $	243	Acer negundo	Manitoba Maple	1	11		F	F	Р	1	retain	lean, poor form, 60% deadw ood
	244	Acer platanoides	Norway Maple	1	11		G	G	G	3	retain	tar spot
	245	Acer negundo	Manitoba Maple	1	16		F	F	F	4	retain	grow ing into tree 236
	246	Acer platanoides	Norway Maple	1	20		G	G	G	4	retain	lack of vigour, tar spot
	247	Acer platanoides	Norway Maple	1	26		G	G	G	4	retain	lack of vigour, tar spot
$\ $	248	Acer platanoides	Norway Maple	1	18		G	G	G	4	remove	
,	249	Acer platanoides	Norway Maple	1	23		G	G	F	4	remove	20-30% deadw ood, tar spot, lack of vigour
	250	Acer negundo	Manitoba Maple	1	22,24		F	G	Р	4	retain	30-40% deadw ood, multi-stem
$\ $	251	Acer negundo	Manitoba Maple	1	26		F	F	Р	4	retain	lean, poor form, 60% deadw ood
$\ $	G-252	Acer platanoides	Norway Maple	5	21,10,10,11		G	G	G	2-4	remove	tar spot, 1) 21, 2) 10, 3) 10, 4) 11, 5) 21
$\ $	253	Acer platanoides	Norway Maple	1	19		G	G	G	3	remove	
$\ $	254	Acer platanoides	Norway Maple	1	15		G	G	G	3	retain	
$\ $	255	Acer platanoides	Norway Maple	1	20		G	G	G	3.5	remove	
$\ $	256	Acer platanoides	Norway Maple	1	18,20,22		F	G	G	3	retain	co-dominant stems
$\ $	257	Acer platanoides	Norway Maple	1	10		F	G	G	2.5	retain	dead w illow leaning on tree
$\ $	258	Acer platanoides	Norway Maple	1	11		G	G	G	2.5	retain	tar spot
$\ $	259	Acer platanoides	Norway Maple	1	10.5		G	G	G	2.5	retain	tar sport
$\ $	260	Acer platanoides	Norway Maple	1	24		F	G	F	3	retain	one stem dead
$\ $	261	Acer negundo	Manitoba Maple	1	28,18,14		Р	F	G	1	retain	80% lean, trunk damage, multi-stem
	262	Acer platanoides	Norway Maple	1	38		G	G	G	6	retain	
	263	Acer negundo	Manitoba Maple	1	18,21,26		F	F	G	6	retain	multi-stem



- 1									
1									
J									
	2	JAN 23, 14	GRCA SUBMISSION	JJZ	ВТ				
	1	OCT 25, 13	FINAL ARBORIST REPORT	JJZ	BT/PM				
	No.	DATE	DESCRIPTION	BY:	CH'KD.				
	ISSUES/REVISIONS								



ENGINEERING SERVICES


YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN TREE INVENTORY AND LANDSCAPE RESTORATION

100 Commerce Valley Dr. West, Thornhill, ON Canada L3T 0A1 t: 905.882.1100 f: 905.882.0055 www.mmm.ca



SCALES:							
HOR: 1:500	VER: _						
DATE DRAWN:							
AUGUS	T 2013						
DRAWN BY: CHECKED BY:							
JJ.Z B.T./P.M.							
CONSULTANT D	CONSULTANT DRAWING No.						
L12							
CITY CONTRACT No.							
12-145							
CITY REFEREN	REV.						



TREE PRESERVATION NOTES AND GUIDELINES

ESTABLISHMENT OF TREE PROTECTION ZONE (TPZ):

- TREE PRESERVATION MEASURES, INCLUDING THE ESTABLISHMENT OF TREE PROTECTION ZONE (TPZ) SHALL APPLY TO THE VEGETATION IDENTIFIED TO BE RETAINED AND PROTECTED. THE TREE PROTECTION ZONE SHALL CONSIST OF TREE PROTECTION FENCING AS PER CITY OF GUELPH STANDARD SD-90A AND SD-90C, PLACED AT THE DRIPLINE OF VEGETATION TO BE PRESERVED. REFER TO DETAILS ON THIS SHEET.
- NO GRADE CHANGES SHALL OCCUR WITHIN TREE PROTECTION ZONE. IN THE EVENT THAT GRADE CHANGES OCCUR EITHER AS A CUT OR FILL SITUATION. THE CONSULTING ARBORIST MUST BE NOTIFIED SO THAT PRECAUTIONS TO PRESERVE THE TREE CAN BE DETERMINED PRIOR TO THE PLACEMENT OF FILL OR EXCAVATION ACTIVITIES.
- EVERY PRECAUTION MUST BE TAKEN TO PREVENT DAMAGE TO TREES AND ROOT SYSTEMS FROM DAMAGE, COMPACTION AND CONTAMINATION RESULTING FROM THE CONSTRUCTION TO THE SATISFACTION OF THE CONSULTING ARBORIST.
- TREES THAT REQUIRE PRUNING TO PERMIT CONSTRUCTION ACTIVITIES WILL BE DONE SO IN ACCORDANCE WITH GOOD ARBORICULTURAL PRACTICES. IN THE EVENT THAT IT IS NECESSARY TO REMOVE ADDITIONAL LIMBS OR PORTIONS OF TREES. AFTER CONSTRUCTION HAS COMMENCED, TO ACCOMMODATE CONSTRUCTION, THE CONSULTING ARBORIST IS TO BE INFORMED AND UNDER THEIR DIRECTION THE REMOVAL IS TO BE EXECUTED CAREFULLY AND IN FULL ACCORDANCE WITH ARBORICULTURAL TECHNIQUES, BY A CERTIFIED ARBORIST.
- ANY DAMAGE TO TREES SUCH AS BROKEN LIMBS, DAMAGE TO ROOTS, OR WOUNDS TO THE MAIN TRUNK OR STEM SYSTEMS ARE TO BE REPORTED TO THE CONSULTING ARBORIST SO THAT THE DAMAGE CAN BE ASSESSED IMMEDIATELY AND MITIGATION CAN BE PROMPTLY IMPLEMENTED.

TREE PROTECTION ZONE:

APPLIES TO TREES LOCATED THE LIMIT OF GRADING OR NOTED OTHERWISE. THESE TREES ARE TO BE PRESERVED AND WILL HAVE SILT / TREE PROTECTION FENCING INSTALLED AT ALONG THE LIMIT OF GRADING / LIMIT OF WORK TO ESTABLISH THE TREE PROTECTION ZONE. ANY DAMAGE TO TREES SUCH AS BROKEN LIMBS, DAMAGE TO ROOTS, OR WOUNDS TO THE MAIN TRUNK OR STEM SYSTEMS ARE TO BE REPORTED TO THE CONSULTING ARBORIST SO THAT THE DAMAGE CAN BE ASSESSED IMMEDIATELY AND MITIGATION CAN BE PROMPTLY IMPLEMENTED. WITHIN A TREE PROTECTION ZONE THERE IS TO BE:

- NO CONSTRUCTION • NO ALTERING OF GRADE BY ADDING FILL, EXCAVATING, TRENCHING, SCRAPING, DUMPING OR
- DISTURBANCE OF ANY KIND. NO STORAGE OF CONSTRUCTION MATERIALS, EQUIPMENT, SOIL, CONSTRUCTION WASTE OR
- DEBRIS WITHIN THE DRIP LINE
- NO MOVEMENT OF VEHICLES, EQUIPMENT NO PARKING OF VEHICLES OR MACHINERY
- NO DIGGING, BORING
- NO RIGGING CABLES SHALL BE WRAPPED AROUND OR INSTALLED IN TREES
- NO CONTAMINANTS WILL BE PLACED OVER ROOT SYSTEM NO CONTAMINANTS WILL BE DUMPED OR FLUSHED WHERE FEEDER ROOTS OF TREES EXIST

WORK WITHIN A TREE PROTECTION ZONE

IF WORK MUST BE CONDUCTED WITHIN A TREE PROTECTION ZONE THE CONTRACTOR SHOULD MINIMIZE SOIL COMPACTION AND MECHANICAL ROOT DAMAGE BY UTILIZING ONE OF THE FOLLOWING FOUR METHODS:

- 1. APPLYING 150-300mm OF MULCH TO AREA. UPON COMPLETION REMOVE EXCESS MULCH LEAVING A 100mm DEPTH LAYER OF MULCH.
- 2. LAYING 20mm THICK PLYWOOD OR 100X100mm WOOD BEAMS OVER A 100+MM THICK LAYER OF
- WOOD CHIP MULCH. UPON COMPLETION REMOVE PLYWOOD AND LEAVE MULCH LAYER IN PLACE. 3. APPLYING 100-150mm DEPTH OF GRAVEL OVER A TAUT, STAKED GEOTEXTILE FABRIC. UPON
- 4. PLACING COMMERCIAL LOGGING OR ROAD MATS ON TOP OF A MULCH LAYER. UPON COMPLETION REMOVE MATS. STONE. GEOTEXTILE. AND MULCH EXCEEDING 100mm THICK WILL BE REMOVED FROM THE TREE PRESERVATION AREA ONCE THE THREAT OF SOIL OR ROOT DAMAGE HAS

TREE PRESERVATION AND PROTECTION RECOMMENDATIONS:

THE SURVIVAL RATES FOR TREES, WHICH ARE IN PROXIMITY TO CONSTRUCTION SITES ARE DEPENDENT ON THE RESULTANT CHANGES TO A VARIETY OF ENVIRONMENTAL AND ANTHROPOGENIC FACTORS. THESE CONSTRUCTION ACTIVITIES BRING ABOUT CHANGES TO A VARIETY OF ENVIRONMENTAL FEATURES INCLUDING THE EXISTING MICROCLIMATE INCLUDING WINDS, TEMPERATURE, SOIL MOISTURE, AMOUNT OF AVAILABLE SUNLIGHT, SOIL QUALITY, AND THE LEVEL OF THE WATER TABLE. INCREASED HUMAN ACTIVITIES MAY ALSO DAMAGE THE STRUCTURE AND / OR PHYSIOLOGICAL ACTIVITIES OF THE TREES. THE FULL EFFECTS OF THE DAMAGE MAY NOT APPEAR UNTIL SEVERAL YEARS AFTER ITS OCCURRENCE. THUS, IT IS ESSENTIAL THAT BOTH VEGETATIVE CLEARING AND PRESERVATION METHODS FOLLOW THE GUIDELINES BELOW AND THOSE GENERALLY ACCEPTED AS KEEPING WITH GOOD HORTICULTURAL AND CONSTRUCTION PRACTICES. THE GUIDELINES ARE SUBJECT TO ADJUSTMENTS DEEMED REASONABLE AND APPROPRIATE CONSIDERING THE PROXIMITY AND NUMBER OF TREES INVOLVED AND THE SITE-SPECIFIC SERVICING REQUIREMENT.

GENERAL RECOMMENDATIONS:

- ALL TREES WITHIN THE TREE PRESERVATION ZONE MUST BE LEFT STANDING. THE TREE REMOVALS MUST BE COORDINATED TO BE COMPLETED OUTSIDE OF THE BIRD NESTING SEASON, MAY 1 TO JULY 31.
- ALL REMOVALS MUST BE FELLED INTO THE WORK AREA TO ENSURE THAT DAMAGE DOES NOT OCCUR TO THE TREES WITHIN THE TREE PRESERVATION ZONE.
- UPON COMPLETING OF THE TREE REMOVALS, ALL FELLED TREES ARE TO BE CHIPPED. THIS WORK MUST BE COMPLETED OUTSIDE OF THE BIRD NESTING SEASON, MAY 1 TO JULY 31.
- TREE PROTECTION FENCING / SILT FENCE MUST BE INSTALLED AS PER THE CITY OF GUELPH STANDARD SILT FENCE DETAIL AND AS SHOWN ON THE APPROVED MUNICIPAL ENGINEERING PLAN. UPON INSTALLATION OF THE FENCING, THE CONTRACTOR WILL CONTACT THE CONSULTING ARBORIST TO REVIEW AN APPROVE THE FENCING AND ITS LOCATION PRIOR TO COMMENCEMENT OF ANY GRADING
- AREAS WITHIN THE TREE PRESERVATION ZONE ARE NOT TO BE USED FOR ANY TYPE OF STORAGE (E.G. STORAGE OF DEBRIS, CONSTRUCTION MATERIAL, SURPLUS SOILS, AND CONSTRUCTION EQUIPMENT). NO TRENCHING OR TUNNELLING FOR UNDERGROUND SERVICES SHALL BE LOCATED WITHIN THE TREE PROTECTION ZONE OR DRIPLINE OF TREES DESIGNATED FOR PRESERVATION WITHIN OR ADJACENT TO THE CONSTRUCTION ZONE.

ROOT PRUNING:

AT THE COMMENCEMENT OF CONSTRUCTION PRUNE ROOTS CLEANLY USING ACCEPTABLE ARBORICULTURAL PRACTICES AND IMMEDIATELY BACKFILL WITH APPROPRIATE MATERIAL. ROOTS OVER 2.5cm DIAMETER THAT ARE TO BE CUT SHOULD BE PRUNED RATHER THAN LEFT TORN OR CRUSHED. THE FOLLOWING ARE GENERAL METHODS OF ROOT PRUNING:

- 1. SOIL EXCAVATION USING SUPERSONIC AIR TOOLS, PRESSURIZED WATER OR HAND TOOLS, FOLLOWED BY SELECTIVE ROOT CUTTING
- 2. CUTTING THROUGH THE SOIL ALONG A PREDETERMINED LINE ON THE SURFACE USING TOOL SPECIFICALLY DESIGNED TO CUT ROOTS
- 3. MECHANICALLY EXCAVATING (e.g. BACKHOE) THE SOIL AND PRUNING WHAT IS LEFT OF THE EXPOSED ROOTS.
- 4. CUTS TO BE MADE WITH HAND PRUNING SHEARS, BY-PASS BLADE, PRUNING SAW. DO NOT USE ANVIL TYPE PRUNERS.

PRUNING PRACTICES:

- ALL LIMBS DAMAGED OR BROKEN DURING THE COURSE OF CONSTRUCTION SHOULD BE PRUNED CLEANLY, UTILIZING BY-PASS SECATEURS IN ACCORDANCE WITH APPROVED HORTICULTURAL PRACTICES. SHOULD THERE BE A POTENTIAL RISK OF TRANSFER OF DISEASE FROM INFECTED TO NON-INFECTED TREES; TOOLS MUST BE DISINFECTED AFTER PRUNING EACH TREE BY DIPPING IN METHYL HYDRATE. THIS PRACTICE IS PARTICULARLY IMPORTANT DURING PERIODS OF TREE STRESS AND WHEN PRUNING MANY MEMBERS OF THE SAME GENERA, WITHIN WHICH A DISEASE COULD BE SPREAD QUICKLY (I.E., VERTICILLIUM WILT ON MAPLES OR FIRE BLIGHT ON GENERA OF THE ROSACEA FAMILY).
- DURING EXCAVATION OPERATIONS IN WHICH THE ROOT AREA IS AFFECTED, THE CONTRACTOR IS TO PRUNE ALL EXPOSED ROOTS CLEANLY. PRUNED ROOT ENDS ARE TO BE NEATLY AND SQUARELY TRIMMED AND THE AREA IS TO BE BACKFILLED WITH CLEAN NATIVE FILL AS SOON AS POSSIBLE TO PREVENT DESICCATION AND PROMOTE ROOT GROWTH. THE EXPOSED ROOTS SHOULD NOT BE ALLOWED TO DRY OUT, AND THE CONTRACTOR SHALL DISCUSS WATERING OF THE ROOTS WITH THE CONSULTING ARBORIST SO THAT THE ROOTS SHALL MAINTAIN OPTIMUM SOIL MOISTURE DURING CONSTRUCTION AND BACKFILLING OPERATIONS, YET SO NOT TO INTERFERE WITH CONSTRUCTION OPERATIONS. BACKFILLING MUST BE WITH CLEAN UNCONTAMINATED TOPSOIL FROM AN APPROVED SOURCE. TEXTURE MUST BE COARSER THAN EXISTING SOILS, AND TO COME INTO CLEAN CONTACT WITH EXISTING SOILS (REMOVE AIR POCKETS,
- ALL PRUNING CUTS SHOULD BE MADE TO A GROWING POINT SUCH AS A BUD, TWIG OR BRANCH, CUT JUST OUTSIDE THE BRANCH COLLAR (THE SWOLLEN AREA AT THE BASE OF THE BRANCH THAT SOMETIMES HAS A BARK RIDGE), AND PERPENDICULAR TO THE BRANCH BEING PRUNED RATHER THAN AS CLOSE TO THE TRUNK AS POSSIBLE. THIS MINIMIZES THE SITE OF THE WOUND. NO STUBS SHOULD BE LEFT. POOR CUT LOCATION, POOR CUT ANGLE AND TORN CUTS ARE NOT ACCEPTABLE.
- TREE ROOTS SHOULD NOT BE EXCAVATED WITHIN THE CRITICAL STRUCTURAL ROOTING AREA. THIS IS THE MINIMUM AREA OF THE ROOT SYSTEM NECESSARY TO MAINTAIN VITALITY OR STABILITY OF THE TREE. TYPICALLY THIS AREA EXTENDS TO THE DRIPLINE OF THE TREE. THE SEVERING OF ONE ROOT CAN CAUSE APPROXIMATELY 5-20% LOSS OF THE ROOT SYSTEM. A REDUCTION OF THIS AREA BY GREATER THAN 30% CAN POSE STABILITY CONCERNS FOR THE TREE.
- A SLOW RELEASE FERTILIZER EG: BONE MEAL OR APPROVED EQUAL TO BE APPLIED TO TREES WHERE ROOT PRUNING OR ROOT DAMAGE HAS OCCURRED. APPLY PER MANUFACTURER'S RECOMMENDATIONS
- EXTENSIVE PRUNING IS BEST COMPLETED BEFORE PLANTS BREAK DORMANCY. PRUNING SHOULD BE LIMITED TO THE REMOVAL OF NO MORE THAN ONE THIRD (1/3) OF THE TOTAL BUD AND LEAF BEARING BRANCHES. PRUNING SHOULD INCLUDE THE CAREFUL REMOVAL
- DEADWOOD
- BRANCHES THAT ARE WEAK, DAMAGED, DISEASED AND THOSE WHICH WILL
- INTERFERE WITH CONSTRUCTION ACTIVITY, SECONDARY LEADERS OF CONIFERS.
- TRUNK AND ROOT SUCKERS, TRUNK WATERSPOUTS, AND
- TIGHT V-SHAPED OR WEAK CROTCHES (INCLUDED UNIONS).

THE CONTRACTOR MUST IMMEDIATELY REPORT ANY DAMAGE TO TREES SUCH AS BROKEN LIMBS, DAMAGE TO ROOTS, OR WOUNDS TO THE MAIN TRUNK OR STEM SYSTEMS SO THAT THE DAMAGE CAN BE ASSESSED IMMEDIATELY.

THE TREE PROTECTION FENCING WILL BE MAINTAINED UNTIL ALL CONSTRUCTION IS COMPLETED, SOILS ARE STABILIZED AND ALL OF THE EQUIPMENT HAS BEEN REMOVED FROM THE SITE.


TREE INJURY:

TYPICALLY TREE ROOTS EXTEND 1.5 TO 3 TIMES BEYOND THE DRIPLINE OF THE TREE AND ARE WITHIN THE TOP 150mm OF THE SOIL. TYPES OF DAMAGE FROM CONSTRUCTION INCLUDE:

- PHYSICAL INJURY SOIL COMPACTION
- SEVERING OF ROOTS
- SMOTHERING OF ROOTS SPLIT OR BROKEN BRANCHES EXCESSIVE PRUNING

SOIL COMPACTION REDUCES PORE SPACE, OXYGEN AVAILABLE TO ROOTS INCREASES CARBON DIOXIDE ACCUMULATION. RESTRICTS ROOT GROWTH AND THE ABILITY TO ABSORB WATER AND NUTRIENTS, AS WELL AS IMPAIRS DRAINAGE.

SMOTHERING OF ROOTS: 90% OF FINE ABSORBING ROOTS ARE WITHIN THE UPPER 150-300mm OF THE SOIL. SMOTHERING WITH THE ADDITION OF SOIL CAN KILL THE ROOTS AND STRESS THE TREE. PHYSICAL INJURY, SPLIT OR BROKEN BRANCHES HINDER THE TREES ABILITY TO COMPARTMENTALIZE (CLOSE) WOUNDS PROPERLY.



	JAN 23, 14	GRCA SUBMISSION	JJZ	ВТ				
	OCT 25, 13	FINAL ARBORIST REPORT	JJZ	BT/PM				
ο.	DATE	DESCRIPTION	BY:	CH'KD.				
	ISSUES/REVISIONS							



ENGINEERING SERVICES

YORK TRUNK SEWER PAISLEY-CLYTHE WATERMAIN

LANDSCAPE NOTES





HOR: 1:500 VER: ATE DRAWN: AUGUST 2013 CHECKED BY RAWN BY: B.T./P.M. JJ.Z CONSULTANT DRAWING No. L14 CITY CONTRACT No. 12-145 ITY REFERENCE No.

TREE TRANSPLANTING CRITERIA AND GUIDELINES

TREE TRANSPLANTING CRITERIA:

TREE CRITERIA FOR TRANSPLANTING IS AS FOLLOWS:

COMPLETION REMOVE GRAVEL AND GEOTEXTILE.

- 1. GENERALLY, TREES WITH 25CM DBH AND LESS CAN BE TRANSPLANTED SUCCESSFULLY. 2. THE TREE NEEDS TO BE LOCATED WHERE ACCESS WITH TREE SPADE EQUIPMENT IS
- AVAILABLE. 3. TREES THAT HAVE A FAIR OR POOR CONDITION ARE NOT RECOMMENDED FOR
- TRANSPLANTING.
- FOR TREES THAT CAN BE TRANSPLANTED: THESE SHALL BE FLAGGED ON SITE BY A CERTIFIED. ARBORIST PRIOR TO SITE DEMOLITION WORKS. THE TREES COULD BE RELOCATED WITHIN ADJACENT LANDS WHERE EXISTING TREES ARE BEING PRESERVED OR IN OTHER AREAS AS APPROVED BY THE OWNER. THE PROPOSED LOCATIONS SHALL BE STAKED BY A CERTIFIED ARBORIST OR LANDSCAPE ARCHITECT. THE TRANSPLANTING SHOULD BE UNDERTAKEN PER STANDARD TRANSPLANTING PROCEDURES (REFER TO TREE TRANSPLANTING GUIDELINES).
- TREES IN POOR HEALTH THAT ARE WITHIN THE LIMIT OF WORK BUT MAY BE RETAINED DURING CONSTRUCTION SHOULD BE CONSIDERED FOR REMOVAL DUE TO THE PROBABILITY OF THE TREE BECOMING A FUTURE HAZARD (FALLING DOWN) AND THE LIKELIHOOD, SHOULD THE TREE FAIL, OF HITTING A TARGET (PEOPLE AND PROPERTY WITHIN THE PARK, ALONG BOULEVARDS
- TREES ADJACENT TO THE PROPOSED AREA OF WORKS ARE TO BE PROTECTED AS PER THE CITY OF GUELPH, MINISTRY OF NATURAL RESOURCES, AND GRAND RIVER CONSERVATION AUTHORITY'S REQUIREMENTS AND DETAILS FOR TREE PROTECTION (ALSO REFER TO MITIGATION MEASURES: TREE PROTECTION DURING CONSTRUCTION, AND EDGE MANAGEMENT).
- THE TREE PRESERVATION PLAN MAKES SPECIFIC RECOMMENDATIONS FOR THE TREES REVIEWED WITHIN THE WORK AREA BASED ON CURRENT DESIGN DRAWINGS, HOWEVER, UNFORESEEN FUTURE DEVELOPMENT CONSTRAINTS SUCH AS SERVICING AND CONSTRUCTION REQUIREMENTS MAY REQUIRE THE REMOVAL OF ADDITIONAL TREES.
- WHERE TREES HAVE CANOPIES OVERHANGING THE WORK AREA, PRUNING OF THE CANOPY AND/OR ROOTS THAT ARE WITHIN THE WORK AREA MAY BE REQUIRED TO FACILITATE CONSTRUCTION WORKS. THIS PRUNING IS TO BE UNDERTAKEN BY A CERTIFIED ARBORIST, AND IN ACCORDANCE WITH STANDARD PROFESSIONAL ARBORIST PRACTICES.
- DURING AND AFTER THE WORKS, THE TREES REMAINING SHOULD BE REVIEWED ANNUALLY AND/OR ON AN AS-NEEDED BASIS FOR HEALTH CONDITION FOR A PERIOD UP TO A MINIMUM OF THREE YEARS, DUE TO NEGATIVE CONSTRUCTION EFFECTS. THE TREES MAY EXPERIENCE A DECLINE IN HEALTH OVER A PERIOD OF MONTHS OR YEARS. TREES FOUND TO BE HAZARDOUS SHOULD BE REMOVED AS SOON AS POSSIBLE TO MAINTAIN A SAFE ENVIRONMENT.

TREE TRANSPLANTING GUIDELINES:

TRANSPLANT PLANT MATERIAL TO FINAL PLANTING LOCATION AS INDICATED ON BUFFER ENHANCEMENT PLAN OR APPROVED EQUAL BY CONTRACT ADMINISTRATOR.

- TRANSPLANT SCHEDULE: THE OPTIMUM TIME FOR TRANSPLANTING TREES IS DURING THE
- COOLER MONTHS IN SPRING AND EARLY FALL. PLANT PIT PREPARATION: REMOVE ALL DEBRIS, STONES, ETC., FROM PITS. PLACE PLANTING
- SOIL IN PIT AND THOROUGHLY FIRM TO A LEVEL UPON WHICH PLANT WILL REST AT PROPER ELEVATION.
 - 1. BALLS LESS THAN 900MM IN DIAMETER: 2 TIMES WIDTH OF BALL AND 225MM DEEPER THAN BALL.
 - 2. BALLS OVER 900MM DIAMETER: THE WIDTH OF THE BALL PLUS 900MM AND AT LEAST 225MM DEEPER THAN BALL 3. SLOPES: MEASURE PIT SIZES ON SLOPES FROM THE LOWER SIDE.
- PLANTING LAYOUT: PROVIDE STAKES AND STAKE OUT ALL TREE LOCATIONS AND PLANTING AREAS. OBTAIN LAYOUT APPROVAL FROM THE LANDSCAPE ARCHITECT PRIOR TO EXCAVATING PLANT PITS.
- ANTI-DESICCANT: ANTI-DESICCANT EMULSION SHALL BE A PRODUCT SPECIFICALLY MANUFACTURED TO PROVIDE A FLEXIBLE SURFACE FILM TO REDUCE TRANSPIRATION YET NOT IMPEDE PASSAGE OF CARBON DIOXIDE AND OXYGEN.

OPEN OR EXPOSED LOCATION.

SETTING PLANTS:

- 1. ONE TO TWO DAYS PRIOR TO TRANSPLANTING, THE TREE SHOULD BE WATERED SO THAT THE SOIL IS SATURATED TO A MINIMUM 300MM DEPTH. 2. SET PLANTS PLUMB AND AT A LEVEL SO THAT AFTER SETTLEMENT THEY
- 3. BACKFILL PITS TO 1/3 DEPTH OF BALL COMPACTING IN LAYERS NOT EXCEEDING 100MM. REMOVE BURLAP AND ADJUST TO AVOID AIR POCKETS. COMPLETE BACKFILL AND SETTLE WITH WATER. 4. AFTER TRANSPLANTING, THE TREE SHOULD BE WATERED SO THAT THE SOIL

BEAR THE SAME GROUND LEVEL RELATIONSHIP AS BEFORE THEY WERE DUG.

IS SATURATED TO A MINIMUM 300MM DEPTH. AFTER THAT, THE TREE SHOULD BE WATERED REGULARLY TO MAINTAIN HEALTH. WHEN POSITIONED IN THE NEW PLANTING PIT, THE TREE SHOULD BE ABOUT 50-75MM ABOVE GRADE TO ALLOW FOR FUTURE SETTLEMENT. 5. TREES TRANSPLANTED FROM A WOODLOT OR FOREST AREA AND/OR

GROWING CLOSE TO OTHER TREES SHOULD NOT BE TRANSPLANTED TO AN

- MULCHING: SPREAD 100MM SHREDDED BARK MULCH OVER FINISHED SURFACE OF EACH PLANT, PLANT BED OR HEDGE TRENCH - WATER PLANTS THOROUGHLY AFTER MULCHING.THE TRANSPLANTED TREE SHOULD BE MULCHED TO A DEPTH OF 100-150MM WITH SHREDDED CONIFEROUS BARK, WITH THE MULCH OFFSET A DISTANCE OF 150MM FROM THE TRUNK. THE MULCH SHOULD BE SPREAD AN AVERAGE OF 100MM PAST THE EDGE OF THE ROOT BALL.
- STAKING: SET TREE STAKES INTO SOLID GROUND BELOW BOTTOM OF PLANT BEFORE BACKFILLING. PLACE STAKES AT THE OUTER EDGE OF THE ROOTS OR BALL IN LINE WITH THE PREVAILING WIND AT A 10 DEGREE ANGLE FROM THE TREE TRUNK THE TRANSPLANTED TREE SHOULD BE STAKED UNTIL THE TREE ROOTS ARE RE-ESTABLISHED, WITH STAKES POSITIONED TO BUTTRESS AGAINST THE PREVAILING WIND.
- WRAPPING: WRAP ALL DECIDUOUS TREES WITHIN 4 DAYS AFTER TRANSPLANTING. WRAPPING MATERIAL FOR TREE TRUNKS SHALL BE NEW BURLAP, AT LEAST 270 G/M2 IN WEIGHT AND NOT LESS THAN 150 MM NOR MORE THAN 250 MM IN WIDTH, OR A HEAVY WATERPROOF CREPE PAPER NOT LESS THAN 100 MM NOR MORE THAN 150 MM WIDE. TREES SHOULD NOT BE TRANSPLANTED ON HOT AND WINDY DAYS. THE FOLIAGE SHOULD BE PROTECTED FROM WATER LOSS DURING THE PROCESS BY WRAPPING WITH TARP DURING TRANSPORTATION.
- SURFACE FINISH: FORM A SAUCER AS INDICATED ON DRAWINGS OR AS DIRECTED. GRADE SOIL TO FORM A BASIN ON LOWER SIDE OF SLOPE PLANTINGS, WHICH WILL CATCH AND RETAIN WATER. TOP DRESS ALL BASINS WITH COMMERCIAL FERTILIZER (10-6-4) SPREAD EVENLY AT THE RATE OF 1KG/SQUARE METRE OF PLANT PIT SURFACE. BREAK BASINS BEFORE GROUND FREEZES.
- PRUNING: PRUNE IMMEDIATELY AFTER PLANTING USING SHARP TOOLS APPROVED BY THE LANDSCAPE ARCHITECT. REMOVE APPROXIMATELY 1/3 OF THE WOOD OF DECIDUOUS PLANTS. MAINTAINING THE NATURAL HABIT OF THE PLANT. CUT NO LEADERS. PAINT ALL PRUNING CUTS 3/4 INCH IN DIAMETER OR OVER WITH ANTISEPTIC, WATERPROOF, ADHESIVE AND ELASTIC TREE WOUND PAINT CONTAINING NO KEROSENE, COAL TAR, CREOSOTE OR OTHER MATERIAL HARMFUL TO CAMBIUM OR LIVING TISSUE.
- GUYING: GUY WIRE TIGHTENERS SHALL BE GALVANIZED TURNBUCKLES OR AN ACCEPTABLE MANUFACTURED DEVICE WHICH TWISTS AND LOCKS GUY WIRES. CONNECT MULTI-STEM TREES WITH PROTECTED CONNECTING WIRES MAINTAINING EACH STEMS RELATIONSHIP TO ONE ANOTHER. MAINTAIN ALL GUYS UNTIL END OF GUARANTEE.
- FERTILIZING: TRANSPLANTED TREES WITH A SLOW RELEASE FERTILIZER EG: BONE MEAL OR APPROVED EQUAL. APPLY PER MANUFACTURER'S RECOMMENDATIONS.

GENERAL NOTES:

- CONTRACTOR TO REMOVE AND DISPOSE OF OFF-SITE AT NO ADDITIONAL COST TO THE CONTRACT ITEMS NOTED FOR REMOVAL INCLUDING BUT NOT LIMITED TO ALL ASPHALT PAVING, CONCRETE CURBS, CONCRETE PAVING, STUMPS, SOD, TOPSOIL, SIGNAGE AND FILL AS REQUIRED TO FACILITATE THE IMPLEMENTATION OF CHANGES AS PER PLANS AND DETAILS. ANY SIGNAGE OR ANY OTHER ITEMS IDENTIFIED BY THE CLIENT TO BE SALVAGED, SHALL BE STORED AT A LOCATION ON-SITE AS IDENTIFIED BY THE CLIENT.
- CONTRACTOR TO MAKE GOOD TO CONTRACT ADMINISTRATOR'S APPROVAL ALL DAMAGES THAT OCCUR DURING CONSTRUCTION.
- CONTRACTOR TO REVIEW DRAWINGS AND REPORT ANY ERRORS, OMISSIONS, AND / OR DISCREPANCIES TO CONTRACT ADMINISTRATOR IN WRITING PRIOR TO CONSTRUCTION. PROPERTY LINES TO BE VERIFIED PRIOR TO INITIATING ANY CONSTRUCTION
- THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES. CONTRACTOR TO VERIFY LOCATION AND PROTECT ALL SERVICES PRIOR TO ANY EXCAVATION.
- EXTENT OF WORK SHOWN IS TO CONVEY INTENT ONLY. EXTENT OF CONSTRUCTION IS TO BE VERIFIED ON SITE PRIOR TO CONSTRUCTION. IF THERE IS AMBIGUITY OR LACK OF INFORMATION, THE CONTRACTOR SHALL IMMEDIATELY INFORM THE CONTRACT ADMINISTRATOR. THE CONTRACTOR MAY BE HELD RESPONSIBLE TO REMOVE ANY CHANGES MADE WITHOUT WRITTEN PERMISSION OF THE CONTRACT ADMINISTRATOR.
- ALL CONSTRUCTION TO BE CARRIED OUT IN ACCORDANCE WITH THE MOST CURRENT DESIGN STANDARDS, CRITERIA, AND SPECIFICATIONS FORM THE ONTARIO BUILDING CODE, THE ONTARIO PROVINCIAL STANDARD DETAIL, THE ONTARIO PROVINCIAL STANDARD SPECIFICATION AND LANDSCAPE ONTARIO.
- CONTRACTOR TO ENSURE PROPER DEPTH OF EXCAVATIONS ACCOMMODATE HARD SURFACE AND LANDSCAPING AS SPECIFIED ON THESE DRAWINGS.
- CONTRACTOR IS RESPONSIBLE FOR ALL FEES ARISING FROM THE COMPLETION OF WORKS CONVEYED BY THESE DRAWINGS AND IN THE SPECIFICATION PACKAGE. FEES INCLUDE BUT ARE NOT LIMITED TO SECURITIES, PERMIT FEES, DEPOSITS, APPLICATION FEES, LETTERS OF CREDIT, OR ANY OTHER RELATED FUNDING REQUIREMENTS.
- CONTRACTOR IS RESPONSIBLE FOR DAMAGE TO ALL UNDERGROUND SERVICES INCLUDING LIGHT STANDARD ELECTRICAL LINES.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CALL A PRIVATE LOCATING COMPANY AND PAY ALL COSTS RELATING TO ALL SERVICES NOT STAKED OUT BY GAS, HYDRO, BELL, AND CABLE.
- SUBSTITUTIONS FROM SPECIFIED PRODUCTS AND MATERIALS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR PRIOR TO THE ORDERING OF MATERIALS.
- THESE DESIGN DRAWINGS ARE PREPARED SOLELY FOR THE USE BY THE PARTY WITH WHOM THE DESIGN PROFESSIONAL HAS ENTERED INTO A CONTRACT WITH.

SITE PREPARATION NOTES

- CONTRACTOR TO ENSURE POSITIVE DRAINAGE OF ALL AREAS WITHIN THE LIMIT OF THE CONTRACT.
- CONTRACTOR TO WORK WITHIN GUIDELINES FOR THE MUNICIPALITY'S NOISE BY-LAWS.
- ANY REFUSE, GARBAGE, OR OTHER DEBRIS ON SITE MUST BE REMOVED AND DISPOSED OF OFF SITE AT THE EXPENSE OF THE CONTRACTOR.
- AREAS TO BE SODDED SHALL BE BACKFILLED WITH NATIVE SOIL TO 150mm BELOW FINISHED GRADE TO ALLOW FOR TOPSOIL INSTALLATION.
- ABSOLUTELY NO STORAGE OF EQUIPMENT OR MATERIALS OUTSIDE OF CONSTRUCTION FENCING.

SEDIMENTATION CONTROL:

- ALL SILTATION CONTROL FENCING SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF EXCAVATION OR GRADING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL SILTATION CONTROL DEVICES IN GOOD WORKING ORDER AT ALL TIMES. CONTRACTOR SHALL INSPECT SUCH DEVICES DAILY AND AFTER EACH RAINFALL EVENT.
- FOLLOWING COMPLETION OF CONSTRUCTION, COLLECTED SILT SHALL BE DISPOSED OFF-SITE, SILT FENCE SHALL BE REMOVED AND THE AFFECTED AREAS SHALL BE RESTORED IN ACCORDANCE WITH THE APPROVED CONSTRUCTION DRAWINGS.
- ALL ON-SITE STORAGE OF GRANULAR MATERIALS WILL BE ISOLATED AND SECURED WITH SILT FENCING
- NO IN-WATER WORKS ARE PERMITTED.
- NO VEHICLES OR EQUIPMENT WILL BE REFUELLED WITHIN 30 METRES OF THE WATERCOURSE.
- NO MATERIAL WILL BE STOCKPILED ON THE WATERCOURSE BANKS.
- THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO PREVENT SEDIMENT RELEASES TO THE NATURAL ENVIRONMENT. THE CONTRACT ADMINISTRATOR SHOULD BE IMMEDIATELY CONTACTED IF THE EROSION AND SEDIMENT CONTROL PLANS CHANGE FROM THE APPROVED PLANS. FAILED EROSION AND SEDIMENTATION CONTROL MEASURES SHOULD BE REPAIRED IMMEDIATELY.

UNDERGROUND SERVICING AND UTILITIES:

- ALL UNDERGROUND SERVICE INFORMATION IS DERIVED FROM RECORDS AND SERVICES HAVE NOT BEEN LOCATED BY THE UTILITY COMPANIES OR BY DAYLIGHTING. MMM GROUP GEOMATICS ONTARIO LIMITED AND MMM GROUP LIMITED ASSUME NO RESPONSIBILITY AS TO THE ACCURACY, CORRECTNESS AND COMPLETENESS OF THE UNDERGROUND SERVICE INFORMATION SHOWN ON THE FACE OF THIS PLAN. UTILITIES MUST BE LOCATED BY THE UTILITY COMPANIES BEFORE CONSTRUCTION BEGINS. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGES WHICH OCCUR TO EXISTING SERVICES DURING CONSTRUCTION.
- CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES ON THE SITE.
- CONTRACTOR MUST CHECK & VERIFY ALL DIMENSIONS AND CONDITIONS ON THE JOB, REPORTING ALL DISCREPANCIES TO THE CONTRACT ADMINISTRATOR BEFORE PROCEEDING WITH THE WORK.
- CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE CAUSED TO EXISTING SERVICES WHEN EXCAVATING.

GRADING NOTES:

- CONTRACTOR TO ENSURE POSITIVE DRAINAGE OF ALL AREAS WITHIN THE LIMIT OF THE CONTRACT.
- ENSURE TRANSITION OF EXISTING AND NEW GRADE ELEVATIONS IS SMOOTH.
- MINIMUM PERMITTED HARDSCAPE SLOPE IS 2%; MAXIMUM PERMITTED IS 5%.
- MINIMUM GROUND SLOPE TO BE 2%, MAXIMUM PERMITTED 33%.
 PROPOSED ELEVATIONS ALONG LIMIT OF CONTRACT MUST MATCH EXISTING ELEVATIONS.
- NOTIFY CONTRACT ADMINISTRATOR IMMEDIATELY, IN WRITING, IF ANY DISCREPANCIES WITH STATED REQUIREMENTS ARE DISCOVERED.

LAYOUT NOTES:

- LAYOUT TO BE STAKED BY CONTRACTOR AND APPROVED BY THE CONTRACT ADMINISTRATOR.
- ALL PLANT MATERIAL TO BE INSPECTED BY CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION. ALL PLANT
- MATERIAL MAY BE REJECTED AT ANY TIME DURING CONSTRUCTION AND WARRANTY PERIOD.

 ALL SEEDING ON SLOPES GREATER THAN 3 (HOI
 GUARD FIBRE MATRIX' TO MANUFACTURER'S SP
 CONTRACTOR TO REVIEW DRAWINGS AND REPORT ANY ERRORS, OMISSIONS, OR DISCREPANCIES TO THE
- PROPERTY LINES TO BE VERIFIED PRIOR TO INITIATING CONSTRUCTION
- SITE FURNISHINGS TO BE AS SPECIFIED UNLESS SUBSTITUTION IS APPROVED IN WRITING BY CONTRACT ADMINISTRATOR.
- NOTIFY CONTRACT ADMINISTRATOR IMMEDIATELY, IN WRITING, IF ANY DISCREPANCIES WITH STATED REQUIREMENTS ARE DISCOVERED.

TOPSOIL PLANTING BED PREPARATION:

- MIX TOPSOIL AS RECOMMENDED BY SOIL TEST RESULTS AND RECOMMENDATIONS OF SOIL TESTING AGENCY.
- TOPSOIL SHALL NOT BE USED TO CONSTRUCT PERMANENT BERMS.
- ALL TOPSOIL SHOULD BE FREE OF SUBSOILS, CLAY, STONES, ROOTS, EXCESS WATER, FROST AND OTHER EXTRANEOUS MATTER.
- PREPARE PLANTING BEDS PRIOR TO ARRIVAL OF PLANT MATERIAL ON SITE.

EXCAVATE PER PLANTING DETAILS. THE FOREGOING PROPORTIONS ARE SUBJECT TO CHANGE UPON RECEIPT OF TOPSOIL ANALYSIS.

PREPARE PLANTING SOIL BY EVENLY MIXING:

CONTRACT ADMINISTRATOR IN WRITING.

- 5 PARTS NATIVE SOIL
- 1 PART SHARP SAND
- 2 PARTS ¹/₄" SCREENED COMPOST
- 500g OF BONE MEAL PER CUBIC METRE.
- MIX THOROUGHLY

SODDING NOTES:

- ALL SOD SHALL BE GUARANTEED FOR 3 MONTHS FROM DATE OF SUBSTANTIAL PERFORMANCE.
- SODDING SHALL CONFORM TO LANDSCAPE ONTARIO'S 'GENERAL LANDSCAPE SPECIFICATIONS'.
- TOPSOIL SHALL BE EVENLY SPREAD OVER SUB-GRADE AND LOOSELY COMPACTED TO 150mm MINIMUM DEPTH.
- ALL STONES AND DEBRIS OVER 25mm DIA. SHALL BE REMOVED.
- TOPSOIL SHALL BE SUPPLEMENTED WITH A 10-6-4 FERTILIZER AND 20% SUPERPHOSPHATE APPLIED AT A RATE
 OF 5 KILOS PER 100 SQUARE METRES EACH, PRIOR TO PLACEMENT OF SOD.
- SOD SHALL BE PLACED WITH STAGGERED BUTT JOINTS, WATERED THOROUGHLY, AND ROLLED WHEN DRY
- LAY SOD SECTIONS PERPENDICULAR ON SLOPES GREATER THAN 3:1 AND SECURE WITH WOODEN PEGS. WOODEN PEGS TO BE 17 X 17 X 300mm. PLACE PEGS 3 PER SQUARE METRE, 100mm BELOW TOP EDGE TO PREVENT SHIFTING OF SOD AND DRIVE PEGS FLUSH WITH TOP OF SOD SOIL. PROVIDE A MINIMUM OF 2 STAKES PER ROLL OF SOD.
- MAINTAIN SODDED AREA FROM THE TIME OF INSTALLATION UNTIL THIRTY (30) CALENDAR DAYS AFTER ALL SODDED AREAS HAVE BEEN INSPECTED BY THE CONTRACT ADMINISTRATOR AND A CERTIFICATE OF COMPLETION IS ISSUED. MINIMUM OF TWO CUTS.
- MAINTENANCE SHALL INCLUDE ALL NECESSARY MEASURES TO ESTABLISH AND MAINTAIN GRASS IN A HEALTHY, VIGOROUS GROWING CONDITION.
- MAINTENANCE SHALL INCLUDE. BUT NOT BE LIMITED TO THE FOLLOWING WORK:
- a. MOWING AT REGULAR INTERVALS TO MAINTAIN A MAXIMUM HEIGHT OF 60MM. DO NOT CUT MORE THAN 1/3 OF THE GRASS HEIGHT AT ANY ONE MOWING. TRIM AND CLIP EDGES. REMOVE CLIPPINGS AFTER MOWING AND TRIMMING.
- b. WATERING WHEN REQUIRED IN SUFFICIENT QUANTITIES AND AT A FREQUENCY TO PREVENT SOD FROM DRYING OUT AND TO MAINTAIN SOIL UNDER SOD CONTINUOUSLY MOIST TO A DEPTH OF 75 TO 100MM.
- c. FERTILIZE SODDED AREAS ONE MONTH AFTER SODDING WITH 2:1:1 RATIO FERTILIZER. SPREAD EVENLY AT A RATE AS PER MANUFACTURER'S INSTRUCTIONS AND WATER IN WELL, WITH A MINIMUM OF 50CM INFILTRATION AS PREVIOUSLY MENTIONED.

TERRASEEDING:

TERRASEDING SHALL BE APPLIED TO ALL AREAS DISTURBED BY THE CONSTRUCTION OPERATION THAT WILL NOT BE COVERED WITH ASPHALT, MULCH, SOD, PATHWAY, OR OTHER SPECIFIED SURFACE. AT TIME OF TERRASEDING, ALL SURFACE AREAS MUST BE UNIFORMLY GRADED AND SHALL BE FREE OF EROSION, STONES GREATER THAN 50mm IN DIAMETER, WEEDS AND ANY OTHER UNWANTED VEGETATION. EXISTING SURFACE SOIL SHALL BE UNIFORMLY CULTIVATED TO A MINIMUM DEPTH 50mm TO PROVIDE A LOOSE AND FRIABLE SEEDBED TO ACCELERATE GERMINATION OF SEED.

THE BLOWER TRUCK SHALL BE EQUIPPED WITH A COMPUTER-CALIBRATED SEED INJECTION SYSTEM AND SHALL BE CAPABLE OF UNIFORMLY APPLYING COMPOSTED TOPSOIL AND SEED AT A RATE GREATER THAN 0.25 m3 PER MINUTE. COMPOSTED TOPSOIL SHALL BE PRE-MIXED AND CONSIST OF A MINIMUM 60% COMPOST MATERIAL.

NOTE:

SEEDING SHALL BE PLACED ON 150mm OF TOPSOIL.

- ALL SEED TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS FOR MULCH, TACKIFIER, AND SPECIFIC SEEDING RATE AND TIMING OF APPLICATION.
- CONTRACTOR TO VERIFY SEEDING RATES RELATIVE TO SOIL TYPE PRIOR TO INSTALLATION OF SEED.
 ALL SEEDING ON SLOPES GREATER THAN 3 (HORIZONTAL): 1 (VERTICAL) SHALL BE PROTECTED WITH 'SC
- ALL SEEDING ON SLOPES GREATER THAN 3 (HORIZONTAL): 1 (VERTICAL) SHALL BE PROTECTED WITH 'SOIL GUARD FIBRE MATRIX' TO MANUFACTURER'S SPECIFICATIONS.

'NATIVE UPLAND FORAGE AND MEADOW MIX' (OSC #8140)

35% CANADIAN WILD RYE
10% FOWL BLUEGRASS (POA PALUSTRIS)
5% FOX SEDGE (CAREX VULPINOIDEA)
5% LITTLE BLUESTEM (SCHIZACHYRIUM SCOPARIUM)
10% SAND DROPSED (SPOROBOLUS CRYPTANDRUS)
35% VIRGINIA WILD RYE (ELYMUS VIRGINICUS)

SEED ALL DISTURBED AREAS IDENTIFIED ON THE DRAWING WITH #8140 NATIVE UPLAND FORAGE AND MEADOW MIX, DISTRIBUTED BY ONTARIO SEED COMPANY (519) 886-0557 OR APPROVED EQUAL. SEED AT RATE OF 25KG/HA. SIMULTANEOUSLY SOW COVER CROP OF ANNUAL RYE GRASS FOR EROSION CONTROL AT A RATE OF 22KG/HA MINIMUM.


ALL PACKING SLIPS MUST BE PROVIDED TO CONTRACT ADMINISTRATOR PRIOR TO SEED PLACEMENT.

PLANT MATERIAL ORDER, DELIVERY AND INSPECTION:

- CONTRACTOR TO CHECK ALL QUANTITIES AND REPORT ANY DISCREPANCIES TO THE CONTRACT
 ADMINISTRATOR IN WRITING. THE QUANTITIES INDICATED ON THE PLAN SUPERCEDE THE TOTALS OF
 THE PLANT LIST
- OBTAIN CONTRACT ADMINISTRATOR'S APPROVAL ON ALL PLANT MATERIAL AT SOURCE OR UPON DELIVERY, PRIOR TO COMMENCEMENT OF PLANTING WORK.
- APPROVAL OF PLANT MATERIAL PRIOR TO PLANTING SHALL NOT IMPAIR THE RIGHT OF THE CONTRACT ADMINISTRATOR TO REJECT PLANTS AFTER PLANTING, WHICH HAVE BEEN DAMAGED, OR WHICH IN ANY WAY DO NOT CONFORM TO THE SPECIFICATIONS.
- SUBSTITUTIONS OF SIZE, OR WITH OTHER PLANT MATERIAL WILL ONLY BE ALLOWED WITH THE WRITTEN APPROVAL OF THE CONTRACT ADMINISTRATOR.
- ALL MATERIAL MUST CONFORM TO THE SIZES SHOWN ON THE PLANT LIST, EXCEPT WHERE LARGER PLANT MATERIAL IS USED WHEN APPROVED BY THE CONTRACT ADMINISTRATOR. USE OF LARGER PLANTS WILL NOT INCREASE THE CONTRACT PRICE. UNDERSIZED MATERIAL WILL BE REJECTED.
- ALL SHRUBS AND TREES SHALL CONFORM TO THE PRESENT STANDARDS OF THE CANADIAN NURSERY TRADES ASSOCIATION FOR SIZE AND SPECIES.
- PLANTS ARE TO BE NURSERY GROWN UNDER PROPER CULTURAL CONDITIONS, IN PARTICULAR WITH RESPECT TO SPACING, PEST AND DISEASE CONTROL, AND BRANCH AND ROOT PRUNING.
- TREES ARE TO HAVE STRAIGHT STURDY TRUNKS.
- TREES SHALL BE WELL BRANCHED AND BALANCED WITH A STRONG CENTRAL LEADER.
- DECIDUOUS SHADE TREES SHALL BE FREE OF BRANCHES FROM GROUND LEVEL TO A HEIGHT OF 1.8M ABOVE THE GROUND.
- TREES WITH OPEN SCARS ARE NOT ACCEPTABLE.
- KEEP ALL ROOTS AND ROOTBALLS MOIST PRIOR TO PLANTING.

PLANT MATERIAL GUARANTEE AND FINAL INSPECTION:

- AT THE COMPLETION OF PLANTING OPERATIONS, REMOVE ALL SURPLUS MATERIAL FROM THE SITE AT NO EXTRA CHARGE TO THE PROJECT.
- MAKE GOOD ALL DAMAGE RESULTING FROM PLANTING OPERATIONS AT NO EXTRA CHARGE TO THE
- PLANT MATERIAL SHALL BE GUARANTEED FOR A MINIMUM OF TWO YEARS FROM THE ISSUE DATE OF THE CERTIFICATE OF COMPLETION.
- ALL PLANTS SHALL BE INSPECTED TWICE, ONCE HALFWAY THROUGH THE GUARANTEE PERIOD, AND AGAIN AT THE END OF THE GUARANTEE PERIOD. PLANTS WHICH, AT THAT TIME, ARE NOT IN HEALTHY VIGOROUS GROWING CONDITION, TO THE CONSULTANT'S APPROVAL, SHALL BE REPLACED AT NO EXTRA CHARGE TO THE PROJECT.
- CONTRACTOR TO CONTACT CONTRACT ADMINISTRATOR AND/OR APPROVAL AGENCY/MUNICIPALITY TO REVIEW PROJECT FOR GUARANTEE INSPECTIONS.



JAN 23, 14 GRCA SUBMISSION JJZ BT
OCT 25, 13 FINAL ARBORIST REPORT JJZ BT/PM
D. DATE DESCRIPTION BY: CH'KD
ISSUES/REVISIONS




ENGINEERING SERVICES

YORK TRUNK SEWER

&
PAISLEY-CLYTHE WATERMAIN
LANDSCAPE NOTES


MMM GROUP


100 Commerce Valley Dr. West, Thornhill, ON Canada L3T 0A1





SCALES:
HOR:
VER:
DATE DRAWN:
AUGUST 2013

DRAWN BY:
DEFINITION OF THE PROPERTY OF THE PROPERT










Scale: N.T.S.



KEY PLAN Scale: NOT TO SCALE



ENGINEERING SERVICES

YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN LANDSCAPE DETAILS

MMM GROUP 100 Commerce Valley Dr. West, Thornhill, ON Canada L3T 0A1

t: 905.882.1100 f: 905.882.0055



HOR: N.T.S. VER: DATE DRAWN: AUGUST 2013 DRAWN BY: CHECKED BY JJ.Z B.T./P.M. CONSULTANT DRAWING No. L16 CITY CONTRACT No. 12-145 CITY REFERENCE No.

TREE PROTECTION ZONE INFORMATION SIGNAGE DETAIL

TREE PROTECTION ZONE

 ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN TREE SPADE PREPARE RECEIVING HOLE-WITH A MIXTURE OF PEAT

> HORTICULTURAL PRACTICES, MUNICIPAL STANDARDS AND TO THE APPROVAL OF THE CONSULTANT.

 ACCURATELY CENTRE TREE SPADE FOR REMOVAL OF TREES

NOTES:

- AFTER LIFTING, ROOTS THAT ARE PROTRUDING SHOULD BE PROPERLY REMOVED USING CLEAN,
- PLANTING WILL BE KEPT TO A MINIMUM, PARTICULARLY ON HOT, DRY OR WINDY DAYS
- UNDER NO CIRCUMSTANCES WILL PLANTS
- REMAIN IN SPADES OVER NIGHT
- ALL DRAINAGE CORRECTION SHOULD BE COMPLETED PRIOR TO TRANSPLANTING

PLANTING HOLES WILL BE DUG WITH THE SAME

- BACKFILL SOIL TO BE SAME OF THAT OF SHARP PRUNING TOOLS ROOTBALL AND ORIGINAL PLANTING SITE ALL PLANT MATERIAL SHOULD BE WATERED THE TIME INTERVAL BETWEEN DIGGING AND
 - AFTER PLANTING TO SUPPLY INITIAL MOISTURE TO ROOTS BUT ALSO TO SETTLE BACKFILL SOIL AND ELIMINATE AIR POCKETS

FINAL PLANTING DEPTH SHOULD BE APPROX.


70-80mm HIGHER THAN ORIGINAL PLANTING DEPTH TO FACILITATE PROPER DRAINAGE

- ALL PLANT MATERIAL WILL BE MULCHED AT PLANTING
- ALL PLANT MATERIAL WILL BE FERTILIZED AT PLANTING, ESPECIALLY AT UPPER 300mm OF ROOTBALL AND WHERE OUTER ROOTS WERE

MACHINE THAT WILL DELIVER THE TREE TYPICAL TREE SPADE TRANSPLANT DETAIL

ALL SPECIES AND SIZES


Scale: N.T.S.




L-16

REV. DATE : REV. BY. : G.F. J C.M.C. **ENGINEERING** INFORMATION SIGNAGE DETAIL

Scale: N.T.S.





DEEMED NECESSARY TO MAINTAIN THE TREES IN A HEALTHY CONDITION. DO NOT PRUNE LEADERS. REMOVE ONLY DEAD, DAMAGED OR INTERFERING BRANCHES. APPLY ANTI-DESSICANT PRIOR TO DELIVERY. CONTRACTOR TO REMOVE ALL TAGS AND LABELS PRIOR TO END OF WARRANTY PERIOD. #12 GAUGE GALVANIZED WIRE ENCASED IN 12mmØ REINFORCED RUBBER HOSE AND SECURED TIGHTLY TO STAKE. CONTRACTOR TO REMOVE IN ONE YEAR. - (2) SOFTWOOD STAKES FOR STREET PLANTINGS 38 x 38 x 2440mm (1 1/2" x 1 1/2" x 8') SET STAKE AT ANGLE AND DRAW VERTICAL. PARK PLANTINGS SHALL USE T-BARS. CONTRACTOR TO REMOVE IN ONE YEAR. PROTECT ROOTBALL SURFACE WITH 75mm COVER OF SHREDDED BARK MULCH. — CUT & REMOVE 1/3 TOP OF BURLAP AND ROPE OR WIRE BASKET. (NYLON ROPE IS NOT PERMITTED). FORM 100mm TOPSOIL SAUCER AND COVER WITH 75mm SHREDDED BARK MULCH. LIGHTLY COMPACTED SOIL MIXTURE TO CONSIST OF EXISTING NATIVE SOIL IN A FRIABLE CONDITION FREE OF LUMPS OR STONES AND ENRICHED WITH 0.2m OF PEAT MOSS, 0.5kg OF BONEMEAL AND 1.0kg OF 15-10-8 FERTILIZER.

*WATER AT TIME OF PLANTING AND WHENEVER

EXTEND STAKE 600mm (2') INTO FIRM GROUND.

PLANT TREE NO HIGHER THAN 50mm (2") ABOVE

ORIGINAL GROUND GRADE TO ALLOW FOR

ALL DIMENSIONS ARE IN MILLIMETRES

UNLESS SHOWN OTHERWISE.

75mm (3") SCARIFIED SOIL MOUND

SETTLEMENT.

DO NOT PRUNE LEADERS. REMOVE (2) T-BARS 2440mm LENGTH. SET ONLY DEAD, T-BAR AT ANGLE AND DRAW DAMAGED OR VERTICAL. CONTRACTOR TO INTERFERING REMOVE IN ONE YEAR. FOR BRANCHES. WINDY AREAS & TREES WITH CALIPER OVER 60mm, USE 3 #12 GAUGE GALVANIZED T-BARS. DO NOT STAKE THROUGH WIRE ENCASED IN 12mm ROOTBALL. DIA REINFORCED RUBBER HOSE AND 150mm DIA. CORRUGATED SECURED TIGHTLY TO PERFORATED PVC PIPE HEIGHT STAKE. CONTRACTOR TO 85cm IN OPEN SPACE SITUATIONS. REMOVE IN ONE YEAR. HEIGHT 20cm FOR STREET TREE PLANTINGS. CUT & REMOVE ROPE AND 1/3 TOP OF BURLAP AND WIRE BASKET (NYLON ROPE IS NOT PERMITTED). FORM 100mm TOPSOIL SAUCER AND COVER WITH 100mm SHREDDED CEDAR BARK MULCH. DO NOT VOLCANO MULCH. PLANTING SOIL MIX AS SPECIFIED - LINE OF ORIGINAL GRADE EXTEND STAKE 600mm (2') INTO FIRM GROUND. 100mm (4") SCARIFIED SOIL MOUND 1500mm MINIMUM

· APPLY ANTI-DESSICANT PRIOR TO DELIVERY.

• PLANT TREE NO HIGHER THAN 50mm ABOVE ORIGINAL GROUND GRADE TO ALLOW FOR

• WATER AT TIME OF PLANTING AND WHENEVER DEEMED NECESSARY TO MAINTAIN TREES IN A

HEALTHY CONDITION.

• ALL TAGS AND LABELS TO REMAIN UNTIL INSPECTION IS COMPLETE. CONTRACTOR TO REMOVE ALL STAKES, TAGS AND LABELS AT THE END OF ONE YEAR.

L-17 / ALL SPECIES AND SIZES

TREE PLANTING ON A SLOPE DETAIL

Scale: N.T.S.

Scale: N.T.S.

DECIDUOUS TREE PLANTING DETAIL L-17 / ALL SPECIES AND SIZES

Scale: N.T.S.

CONIFEROUS TREE PLANTING DETAIL ALL SPECIES AND SIZES

1200 TYP.

Scale: N.T.S.

PRUNE IN SUCH A MANNER AS TO PRESERVE THE NATURAL CHARACTER OF THE PLANT. REMOVE FROM POT OR CONTAINER, OR CUT AND REMOVE BURLAP FROM TOP 1/3 OF ROOT BALL. 75mm DEPTH OF SHREDDED BARK MULCH TO DRIP LINE. CONSTRUCT TOPSOIL SAUCER 100mm HIGH AROUND SHRUB BASE OR SHRUB BED. **EXISTING TOPSOIL** PLANTING SOIL MIX AS SPECIFIED BACKFILL SOIL TO BE COMPACTED TO PREVENT AIR POCKETS AND SCARIFY SURFACE OF SUBSOIL


PRIOR TO PLANTING.

NOTES:

- 1. PLANTING METHOD ILLUSTRATED SHALL APPLY EQUALLY TO BARE ROOT AND BALLED STOCK. 2. SET SHRUBS 50mm HIGHER THAN SURROUNDING GRADE TO ALLOW FOR SETTLEMENT.
- 3. THE ABOVE DETAIL DOES NOT REPRESENT ANY PARTICULAR SPECIES.
- 4. SHRUBS PLANTED IN GROUPS SHALL BE SET IN CONTINUOUS BEDS.
- 5. ALL MEASUREMENTS ARE IN MILLIMETRES UNLESS OTHERWISE INDICATED.


ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE.

SHRUB PLANTING DETAIL ALL SPECIES AND SIZES



- APPLY ANTI-DESSICANT PRIOR TO DELIVERY. PLANT TREE NO HIGHER THAN 50mm ABOVE ORIGINAL GROUND GRADE TO ALLOW FOR
- WATER AT TIME OF PLANTING AND WHENEVER DEEMED NECESSARY TO MAINTAIN TREES IN A
- HEALTHY CONDITION. • ALL TAGS AND LABELS TO REMAIN UNTIL INSPECTION IS COMPLETED.
- CONTRACTOR TO REMOVE ALL TAGS, LABELS AND STAKES AT THE END OF ONE YEAR.


SHRUB PLANTING ON A SLOPE DETAIL ALL SPECIES AND SIZES



TERRASEEDING DETAIL

Key	Qty.	Botanical Name	Common Name	Size	Condition	Remarks
Trees	•	-				
eciduous						
Ar	28	Acer rubrum	Red Maple	45mm Cal	W.B	
As	50	Acer saccharum	Sugar Maple	45mm Cal	W.B	
Asa	25	Acer saccharinum	Silver Maple	45mm Cal	W.B	
Jn	30	Juglans nigra	Black Walnut	45mm Cal	W.B	
Qa	23	Quercus alba	White Oak	45mm Cal	W.B	
Qr	36	Quercus rubra	Red Oak	45mm Cal	W.B	
Sn	7	Salix nigra	Black Willow	45mm Cal	W.B	
oniferous	•	-				
Pg	15	Picea glauca	White Spruce	200cm ht	W.B	
Ps	6	Pinus strobus	Eastern White Pine	200cm ht	W.B	
Shrubs						
cs	45	Cornus sericea	Red Osier Dogwood	50cm, 3gal.	pot	1.5m o.c.
ро	66	Physocarpus opulifolius	Eastern Ninebark	50cm, 3gal.	pot	1.5m o.c.
sb	18	Salix bebbiana	Bebb's Willow	50cm, 3gal.	pot	1.5m o.c.
se	38	Salix eriocephala	Heart-leaved Willow	50cm, 3gal.	pot	1.5m o.c.
sc	48	Sambucus nigra ssp. canadensis	Common Elderberry	50cm, 3gal.	pot	1.5m o.c.
to	30	Thuja occidentalis	Eastern White Cedar	50cm, 3gal.	pot	1.5m o.c.

30 I huja occidentalis Eastern White Cedar 50cm, 3gal. pot 1.5m o.c. Note: Each shrub must be a minimum 3-stem specimen. Plant Quantities Indicated on the Planting Plan will Supercede the Quantities Listed Above.



KEY PLAN Scale: NOT TO SCALE




ENGINEERING SERVICES

YORK TRUNK SEWER

PAISLEY-CLYTHE WATERMAIN LANDSCAPE DETAILS








12-145 CITY REFERENCE No.

Scale: N.T.S.

Scale: N.T.S.



SURFACE TREATMENT VARIES REFER TO LAYOUT PLAN EXCAVATION TO BE 300mm WIDER THAN FINISHED PAVEMENT WIDTH

HAND TAMP OUTER EDGE OF ASPHALT TO 45°WHERE ASPHALT MEETS SOFT LANDSCAPING. TO BE CUT FLUSH WHERE ADJACENT TO 2% CROSS SLOPE TYPICAL. REFER TO GRADING PLAN 90mm ASPHALTIC CONCRETE: 35mm HL3 SURFACE COURSE 55mm HL4 BINDER COURSE ASPHALTIC CONCRETE PAVING MATERALS TO CONFORM TO OPSS 1150 ASPHALT PLACEMENT AND COMPACTION AS PER OPSS 310

150mm GRANULAR 'A' BASE COURSE: CONFIRM SAMPLES AS PER OPSS 1010 PRIOR TO UTILIZATION ON SITE, COMPACTED TO 100% SPMDD

CONFIRM SAMPLES AS PER OPSS 1010 PRIOR TO UTILIZATION ON SITE, COMPACTED TO 100% SPMDD

UNDISTURBED OR COMPACTED SUBGRADE TO 95% SPMDD NOTE: ANY FILL REQUIRED TO RAISE GRADES TO BE PLACED IN 300mm LIFTS AND COMPACTED TO 95% SPMDD

1. PRIOR TO CONSTRUCTION OF ASPHALT DRIVEWAY, PARKING AREAS,
AND/OR PATHWAYS, EXISTING SURFICIAL TOPSOIL TO BE REMOVED AND SUBGRADE PROOF-ROLLED AND INSPECTED BY GEOTECHNICAL ENGINEER.

 ALL DIMENSIONS SHOWN IN MILLIMETRES
 DO NOT BACKFILL AGAINST ASPHALT MINIMUM 48 HOURS UNTIL ASPHALT HAS CURED

- VERY COURSE SAND OR FINE GRAVEL

- NATIVE BACKFILL MATERIAL

100mm 19mm CLEARSTONE ALL

150mm DIAMETER "BIG-O" PERFORATED DRAINAGE TUBING AS INDICATED ON PLAN. TO OUTLET LOCATION. MINIMUM 0.5%

AROUND PIPE - GEO-TEXILE FABRIC- TERRAFIX 270-R OR EQUAL

PER USGA SPECS

4. THIS DETAIL IS TO BE USED IN CONJUNCTION WITH SPECIFICATION SECTION: ASPHALT PAVING




Scale: N.T.S.


Scale: N.T.S.

ASPHALT PAVING DETAIL

Scale: N.T.S.

Scale: N.T.S.






LIMESTONE SCREENING TRAIL DETAIL

L-18

BIG "O" DETAIL

\ L-18

TOOM 1800 IN 1



KEY PLAN Scale: NOT TO SCALE



ENGINEERING SERVICES

YORK TRUNK SEWER PAISLEY-CLYTHE WATERMAIN

LANDSCAPE DETAILS





	SCALES:							
	HOR: N.T.S.	VER:						
	DATE DRAWN:							
	AUGUST 2013							
	DRAWN BY:	CHECKED E						
	JJ.Z	B.T./P.M.						
	CONSULTANT DRAWING							
	L18							
	CITY CONTRACT No.							
	12-145							
	CITY REFEREN	CE No.	RI					
- 1								